



WELCOME TO THE DESIGN ESSENTIALS

The Design Essentials form part of your Contract of Sale and assist when designing your home and landscape. They are designed to create an attractive streetscape that results in a cohesive urban form, while not precluding individual design solutions.

Stockland encourages a variety of architectural styles and materials in the design of your home. Stockland reserves the right to approve works which do not comply with the Design Essentials where considered to be of merit and to vary the requirements of the Design Essentials at its discretion.

The Design Essentials apply in addition to, and not in lieu of other statutory requirements. Approval from your Local Government Authority or a registered building certifier will be required in addition to any approval given by Stockland.

THE APPROVAL PROCESS

Step 1 - Stockland Design Essentials Approval

Before undertaking any building work, you must first obtain written approval from Stockland. In addition to these 'Design Essentials', your builder or architect will need to review the documentation applicable to your property, which is available in the Reference Library of Stockland's online design application system "i-Scope". They will also be required to discuss with your Local Council any specific codes or conditions which may apply to your lot.

Your builder or architect will submit your design to Stockland via the i-Scope website, www.stockland-iscope.com.au. Stockland will issue a 'Design Approval' where the plans appropriately comply with the Design Essentials. Where not suitably complying, Stockland will identify the items requiring further consideration. Where amendments are necessary, revised plans are to be submitted to Stockland for approval before you can build.

Step 2 – Local Building Approval

Upon receipt of your approval from Stockland, an application can be made to the relevant authority to receive approval for building.

THE DESIGN ESSENTIALS

Siting requirements	<ul style="list-style-type: none"> For siting and setback requirements please see 'Statutory Requirements' contained in the Plan of Development in <i>Annexure 1</i>. For lots with a north and east orientated frontage, dwellings may be sited towards the rear of the lot thereby creating for private recreation space between the street front property boundary and building line. Please refer <i>Annexure 2</i>.
Dual Living Home requirements	<ul style="list-style-type: none"> Dual Living Homes for the stages mentioned within this Design Essentials Booklet are only permitted on lots with a street frontage of 14mtrs or greater. A Dual Living Home must have the design effect of one (1) single residential dwelling from the road/street frontage or within public view. The primary dwelling is permitted to have one (1) entry door visible from the street. The Dual Living entry door must be hidden from view from the street frontage to give the effect that the home is one (1) single residential dwelling. The Dual Living Home is to remain on one (1) title and cannot be strata titled. The primary dwelling is to be greater in size (m²) to the Dual Living Home. The m² size of the Dual Living Home is permitted to be a minimum of 45m² to a maximum of 75m² only. The m² size of the Dual Living Home excludes the garage and a 4m² size covered entry porch area only. All other under roofed areas of the home is included in the m² size of the Dual Living Home. The requirement of a 5000ltr water tank is to be applied to the dwelling treated as one (1) combined dwelling. The water tank is to comply with the requirements included under Water Tank requirements within this document.
Glazing to the street requirements	<ul style="list-style-type: none"> The façade area (excluding the garage door) facing a street or public area is to include sufficient glazing (minimum 10%) to allow for passive surveillance of the street. The facade must incorporate at least one (1) opening to allow for cross ventilation.
Front Façade Articulation and Design (including garage requirements)	<ul style="list-style-type: none"> Façade Repetition of homes within the same street. Stockland reserves the right to ensure there is no repetition of the same front facade within two houses either side of a home and the equivalent on the opposite side of the street across from a home. Walls may be up to 7.5m long before a change in setback and eave line of at least 450mm is required. This includes ground floor and 1st floor front facades. The primary entry is to incorporate a covered roof area with a minimum depth of 1.5mtrs. A covered roof/porch area may be reduced to a depth of 1mtr where a gatehouse is incorporated into the front fencing in accordance with the requirements within this document. <p><u>Garage Requirements:</u></p> <ul style="list-style-type: none"> Garages on single storey homes are to be setback a minimum 450mm behind the front building line of the home. Garages on single storey homes are permitted to be constructed forward of the building line to a maximum of 1mtr where a front fence is to be constructed out to the front boundary of the lot and be constructed forward of the garage. This fencing is to meet the front fence requirements within this document. Garages on single storey homes are permitted to be constructed forward of the building line greater than 1mtr where a front fence is to be constructed out to the front boundary of the lot and be constructed forward of the garage. This fencing must incorporate a gatehouse and is to meet the front fence and gatehouse requirements within this document.

Front Façade Articulation and Design (continued - including garage requirements)	<ul style="list-style-type: none"> Garages on corner allotments are permitted to be constructed forward of the building line however will need to include additional landscaping in addition to the minimum landscaping requirement to be met. Garages on double storey homes are permitted to be constructed forward of the building line where the first (1st) floor of the home is to be constructed as EITHER a cantilever design with an overhang over the garage of 1.0mtr (excluding eaves) OR the first (1st) floor is to be constructed within at least 1.0mtr of the ground floor garage wall for this requirement to be approved. For two storey homes, the upper storey must extend for at least 50% of the total width and length of the home as viewed from the street or roadway and the upper storey facing the street or roadway must have sufficient glazing proportional to the size of the upper storey as determined by Stockland.
Secondary Street Façade Design Articulation	<ul style="list-style-type: none"> On Secondary Street Facades (not limited to corner lots) walls may be up to 7.5mtrs long before a change in setback and eave line of at least 450mm is to apply. This requirement includes facades visible from road reserves, easements, public walkways/footpaths and parks.
Garages and Carports	<ul style="list-style-type: none"> Freestanding or attached carports and garages must include a roof design and design features which are consistent with the form and materials of the home. These items are to meet the setback requirements for garages. Carports must allow lock up and screened storage when visible from the front and secondary street facades.
External Wall Finish requirements	<ul style="list-style-type: none"> Homes are to be constructed to reflect contemporary Queensland Architecture and have regard to the climatic conditions of the area and the estate's unique location. The use of other building materials such as cladding or other contemporary building products are encouraged and can be applied to the home. Building materials selected must be displayed on the plans at time of plan submission for covenant approval. All other External Wall Finish requirements are to be met. External house walls in masonry (with the exception of face brick) for the front and secondary street facades are to be rendered. Side and Rear house walls in masonry are permitted to be bagged and painted. (Please note, if the home has a secondary façade, 1st floor level/s on double storey homes or any façade visible from a main collector road, public space, walkway, park or road frontage then bag and paint is not permitted). As a feature, there is to be either 2 different materials and/or 2 different colours to be applied to the front and secondary street external wall facades of the home. Garage doors, front entry doors, window frames, roof gables and infill materials do not form part of the two (2) different materials and/or two (2) different colours to be applied. Where face brick is chosen the brick must be uniform in colour, smooth in shape and include a complimentary mortar. Natural mortar (Grey in colour) is not permitted. A non permitted brick type listing can be obtained from the Stockland Sales Professional or your chosen Builder. Plans submitted for approval must detail the brick type, colour selection and mortar information at time of plans submission. Approval of other brick and/or mortar type is at the sole discretion of Stockland. Double height face brick is not permitted. Unfinished 'common' bricks are not permitted.

Water Tank requirements	<ul style="list-style-type: none"> • A mandatory requirement is that all homes within the Aura Community are to have a water tank installed at time of construction. • The requirement of a 5000ltr water tank is to be applied for all Detached Homes. The requirement of a 3000ltr water tank is to be applied for all Attached Homes ie: Duplex's or Terraces. • Rainwater Tanks must receive rainfall from at least one half of the roof catchment area. Rainwater Tanks must supply water for external use and internal use to toilet cisterns, laundry and external fixtures. • The water tank is to be displayed on the site plan at time of plan submission for covenant approval as siting requirements for all water tanks are to be checked with the covenant assessment.
Roof Form and Colour requirements	<ul style="list-style-type: none"> • As a positive energy efficiency requirement all homes within the Aura Community are to meet the criteria for "Cool Roof" requirements. • All house roofs within the Aura Community will need to meet a solar absorptance rating of less than 0.5. The solar absorptance rating is included in each roof companies selection brochures to assist Stockland purchasers to make their selection to meet this rating score. • Roofing must be of a scale, colour and form representative of contemporary Queensland Architecture. • 30 degrees is the maximum pitch for any roof. • 15 degrees is the maximum pitch for the main skillion roof.
Driveway requirements	<ul style="list-style-type: none"> • All crossovers and driveways are to be completed prior to occupation. • Driveways must not be a plain concrete finish. A painted driveway is not permitted. • There is to be no movement of any driveway location. Individual driveway locations are approved and displayed on the Plan of Development and Building Envelope Plan. If a driveway is adjusted, any movement can only apply to the standard setback of the lot. A change to driveway locations can disrupt on street parking, tree planting locations, letterbox locations and driveway locations on adjoining lots.
Access to Letterbox requirements	<ul style="list-style-type: none"> • All properties must provide clear access for a postal delivery motorbike to deliver mail to their letterbox. • If properties have a garden feature or bio pod adjoining their property boundary the letterbox must be orientated towards the driveway and not orientated out towards the front property boundary. This will allow for postal deliveries to occur safely and efficiently to the letterbox. • If the letterbox is effected by these items and is not orientated for ease of delivery, postal items may not be delivered to the property.

Landscaping requirements	<ul style="list-style-type: none"> • A maximum of 50% of the front and secondary property boundaries (not including driveways, decks or paths) is to be turfed. • The remaining 50% (or greater) of the front and secondary street property boundaries are to apply a mixture of shrubs, plants and trees. • For Villa and Premium Villa lots, there must include a minimum of 2 x 1.5mtr high plants or trees (at time of planting) between the property boundary and front of the house. A minimum of 1 of these species must be selected from the approved tree species list included in <i>Annexure 3</i> of this document. • For Courtyard, Traditional and Premium Traditional Lots, there must include 3 x 1.5mtr high plants or trees (at time of planting). A minimum of 2 of these species must be selected from the approved tree species list included in <i>Annexure 3</i> of this document. • For all lots, the balance of the 50% planting area must include grasses, groundcovers and/or shrubs at a coverage of approximately 4 plants /m². • All landscaping to the front and secondary property boundaries (if not included in the building contract by the builder) are to be completed within 6 weeks of occupation to the home. • A Landscaping Plan matching the above requirements must be submitted at the time of plan submission for Covenant Approval to be obtained.
Fencing General (incl screening)	<ul style="list-style-type: none"> • Please ensure all proposed fencing is discussed with your adjoining neighbour prior to construction. Please refer to the relevant Neighbourhood Disputes Resolution Act 2011 and/or any guidelines in your State & Local Government regarding fencing requirements. • Please ensure all fencing is constructed at a maximum of 1.8mtrs in height. There is to be no extensions or screening devices that are applied to any fence to exceed 1.8mtrs in height. Any extension, screening or additional materials attached to the top of any fencing will be in non compliance of the covenant. Any such item will be required to be removed by the owner of the property at the owners expense.
Front Fencing requirements (incl Gatehouses)	<ul style="list-style-type: none"> • All front fencing to be constructed will require a covenant approval to be obtained by the Stockland Covenant Department prior to construction. • All front fencing is to be displayed on the site plan at time of plan submission for assessment and approval. • Front fencing is to be a maximum of 1.8m in height. • Any front fencing greater than 1.2mtrs in height is to apply at least a minimum of 50% transparency to the complete length of the fence. • All Courtyard, Traditional and Premium Traditional lots are to apply design features within the front fencing ie: articulation with design features, planters or stepped garden beds to create a design feature for each 3mtrs of front fencing. • Front fencing must not include any unfinished materials. Timber fencing must be painted. Masonry is to be rendered and painted and is to incorporate feature elements. Refer <i>Annexure 2</i> for suggested fencing design. • Front fencing may not be of colourbond construction. • Where there is no front fence constructed the side fence must return to the side of the house a minimum of 1mtr behind the side building line. • Front fencing may incorporate a roofed gatehouse, where the gatehouse has a maximum area of 4m², has a street elevation of not more than 2m wide and is not more than 3m in height. The gatehouse is to incorporate the house number and letterbox.

Secondary Street Fencing requirements (not limited to Corner Lots)	<ul style="list-style-type: none"> • Secondary street fencing is to be a maximum of 1.8m in height. • Is to be capped to the top section of the fence and returns with the same material as the secondary fence material. • Must not include any unfinished materials ie: timber must be stained or painted; masonry is to be rendered and painted. • Secondary fencing may be of colourbond construction limited to certain colour requirements only. A non permitted colourbond fencing colour listing can be obtained from the Stockland Sales Professional or your chosen Builder. Plans submitted for approval must detail the colour of the colourbond fencing at time of plan submission. • Where there is no front fence to be constructed, the secondary/corner side fence must return to the side of the house a minimum of 1mtr behind the side building line. • Where the side boundary of a lot forms the rear boundary of an adjoining lot (usually a corner lot) the side fence may continue to the front of the lot. • Fencing details are to be displayed on the site plan at time of plan submission.
Side & Rear Fencing requirements	<ul style="list-style-type: none"> • All side and rear fencing is to be a maximum of 1.8m in height. • Where there is no front fence to be constructed, the side fence must return to the side of the house a minimum of 1mtr behind the side building line.
Developer Works (Including Retaining Walls, Fencing, Parks or Entry Statements)	<ul style="list-style-type: none"> • Where the developer has constructed a fence, entry statement or retaining wall, it is to be maintained by the owner to the standard to which it was constructed by the Developer. • All fencing connected to any developer fencing must taper for the final 3mtrs to meet the height of the developer fencing
Retaining Walls	<ul style="list-style-type: none"> • Please discuss all proposed retaining walls with your adjoining neighbour prior to construction. Please ensure that the height of the retaining is appropriate to suit the finished ground levels on all adjacent blocks. • Retaining walls visible from the street, park or public space areas are to be constructed from masonry with a rendered and painted finish and/or stone only. Where the height of the wall is less than 300mm and is not visible from the above listed area the retaining wall can be constructed of timber sleepers.
Outbuildings (including sheds and structures)	<ul style="list-style-type: none"> • All outbuildings and sheds must be constructed behind the front or secondary street building line of the home and are not to be visible from the front and secondary street or any public area. • All outbuildings including sheds must be displayed on the site plan at the time of plan submission for a Covenant Approval to be obtained prior to construction. • All structures including but not limited to gazebo's, alfrescos, patios, verandahs and porch areas including extensions or renovations which are to be applied to the home after builder handover or after the original plans for the lot have been covenant approved the owner and builder will be responsible for obtaining a covenant approval for these structures prior to construction. Items including but not limited to: location and siting of the structures, material, size and height, site coverage, external material and colours will need to be checked and approved prior to construction. These structures may also require a Council approval and building permit prior to construction which will be the owner and builders responsibility. • Sheds must be of a colour complimentary to the main home or roof colour. Unfinished metal sheds of any size are not permitted. Any shed larger than a 3mtr x 3mtr garden shed will need to apply the standard setbacks for the lot and may require a council permit and be taken into consideration for the site coverage % of the lot also.

Clothesline	<ul style="list-style-type: none"> • An external clothesline is to be included to each home in the Aura Community. The external clothesline will need to be clearly displayed on the site plan at the time of plan submission. • All clotheslines must be constructed behind the front or secondary street building line of the home and are not to be visible from the front and secondary street boundaries or any public areas.
Non-Ground Mounted Plant or Equipment	<ul style="list-style-type: none"> • Roof mounted items visible from the street or public spaces must be minimal including but not limited to: satellite dishes, TV aerials, hot water services, air conditioning units, heating units. Solar panels and collectors for hot water units are the exception when orientated to maximise their effectiveness.
Ground Mounted Plant or Equipment (Inc rubbish bin storage, water tanks and sheds)	<ul style="list-style-type: none"> • All ground mounted services are not to be visible from any street or public space. This includes but is not limited to homes constructed on corner lots, visible from easements, walkways/footpaths, parks and road reserves. These items may include: heating & cooling units, rubbish bins or compost bins, swimming pool equipment, gas bottles, rain water tanks, clothes lines and sheds. • If bin storage is proposed on a small house design which does not have side access only, a bin storage enclosure is to be designed to completely screen the bins to be non transparent through the screen completely. The bin location and screening device is to be included on the site plans at time of plan assessment for a covenant approval to be obtained prior to construction.
Energy Efficiency requirements	<ul style="list-style-type: none"> • All dwellings are to be wired with an “off-peak” energy circuit enabling the general household appliances to be connected at the discretion of the home owner. • All pool/spa pumps are to be 5 star energy rated or connected to “off-peak” energy circuits. • All split system air conditioners are to be “peak smart” enabled and activated. • All hot water systems are to be connected to “off peak” energy circuits unless solar hot water is installed and/or LP Gas continuous flow hot water systems.
Acoustic requirements	<ul style="list-style-type: none"> • Some lots within the Aura Community are potentially impacted by road traffic noise. These lots are marked on the Plan of Development in <i>Annexure 1</i>. • For affected lots, dwellings must be designed such that internal noise levels comply with AS/NZS2107-2000 ‘Acoustics – Recommended design sound levels and reverberation times for building interiors’.
National Broadband Network (NBN)	<ul style="list-style-type: none"> • AURA will be supplied with NBN network. In-house wiring must comply with the requirements of NBN in-home wiring guide including Home Distributor, Conduiting, Category 6 wiring and power supply. • The owner and the builder will be responsible for these requirements with the owner to speak with their chosen builder if any additional wiring to the home internally and externally is to be provided at time of house construction.
Sewer or Manhole Zone of Influence requirements	<ul style="list-style-type: none"> • Please ensure all works that are carried out which are adjacent to any sewer or manholes including but not limited to landscaping and earthworks are to be applied and to ensure that the sewer or manhole is not impacted upon. • This may include covering, burying, modifying, changing and causing damage to the manhole. Any works carried out that impact on the manhole will need to be rectified at the property owners expense.

<p>Presentation and Maintenance of your lot and completed home</p>	<p>An owner/builder must not permit; cause or authorise any damage to:</p> <ul style="list-style-type: none"> • any adjoining lot and/or • any other part of the Aura Community including but not limited to footpaths, kerb and channel, roadways and/or landscaping. <p>Where such damage occurs and Stockland is required to undertake repairs and rectifications, the owner/builder of the lot will be responsible to pay the cost of these works.</p> <p>Your property must be kept in a clean and tidy state at all times. Silt fences and rubble driveways are in place and must be maintained during the total construction of your home.</p> <p>Where rubbish, soil and grass cuttings are washed or blown from your lot and Stockland determines it is necessary to remove this rubbish, you will be responsible to pay for the cost of the removal.</p> <p>The owner/builder must maintain an industrial waste bin or fully wrapped cage bin on site at all times. The bin is to be established on site as soon as construction has commenced.</p> <p>This waste bin must be regularly emptied and must be covered when full so no material escapes the waste bin.</p> <p>The site must be cleared of any rubbish or building material on a daily basis with this rubbish and building material placed into the waste bin each afternoon when building activity has finished for the day.</p> <p>No excavated material, rubbish or dumping shall be placed on any adjoining lot, private or public area within Aura.</p> <p>For vacant lots that have been sold and settled, the individual owner is responsible for the presentation of the lot. Should excavated material or rubbish be dumped upon the lot, the owner is to address this directly with the adjoining owners/builders.</p> <p>When the home is constructed, the owner is responsible for maintaining the front and secondary street frontages. All turf and garden areas are to be kept mowed and maintained and is the owners responsibility.</p>
-------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------


GLOSSARY OF TERMS

'Common' Brick	<ul style="list-style-type: none"> Brick made for general building purposes and not specially treated for colour and texture.
Front Building Line	<ul style="list-style-type: none"> The line of the closest point to the front boundary either measured to the wall of the house or the Outer Most Structure (including but not limited to porticos, porch or verandahs). The Outer Most Structure excludes gatehouses constructed within the front property boundary or front setbacks.
Façade Area	<ul style="list-style-type: none"> Façade Area is calculated as a square meter measure of the entire vertical surface of the elevation of the house visible from the Street or Public Area.
Glazing	<ul style="list-style-type: none"> Any fixed or opening panel made from glass.
Eave Line	<ul style="list-style-type: none"> As explained in the Plan of Development attached <i>Annexure 1</i>.
Setback	<ul style="list-style-type: none"> The distance measured from adjacent boundary of the lot to the wall of the home as per the Plan of Development setback requirements.
Public Area	<ul style="list-style-type: none"> Any area accessible to the public including but not limited to parks, conservation areas, walkable waterfront, walkways/footpaths and easements.
Building and Other Legislation Amendment Act 2009	<ul style="list-style-type: none"> The Design Essentials are to be read and applied subject to the requirements of the Building and Other Legislation Amendment Act 2009 (Act). If any term, requirement or condition in these Design Essentials (or any part of them) is invalid or unenforceable for any reason (including as a result of the application of the Act) the remaining terms, requirements and conditions will continue to apply and will be valid and enforceable to the fullest extent permitted by law.

ANNEXURE 1

Statutory Requirements

- Plan of Development



PLANS AND DOCUMENTS
referred to in the POA APPROVAL
8 APR 2016

- Land Use**
- District Centre Commercial
 - P-6 State School
 - 7-12 State School
 - Childcare
 - Mixed Use
 - Emerging Community
 - Telecommunications Site
 - Integrated Tourism Attraction

- Open Space**
- Pedestrian Link / Buffer (in road reserve)
 - Local Linear Park
 - District Recreation Park (Linear)
 - Town Square (Civic Square / Local Linear Park)
 - Neighbourhood Recreation Park
 - Drainage Corridors
 - Neighbourhood Sports Park
 - Major Recreation Park
 - Environmental Protection (EPZ)
 - EPZ within Major Recreation Park
 - Conservation Buffer

- 32m Deep Lots**
- Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m
 - Large Lots >32m Deep

- 30m Deep Lots**
- SOHO 10m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m

- 28m Deep Lots**
- Terrace 5m Laneway
 - Terrace 7.5m Laneway
 - Terrace 9m Laneway
 - Detached 10m Laneway
 - Detached 12m Laneway
 - Mode 8.5m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m

- 25m Deep Lots**
- Terrace 7.5m
 - Terrace 9m
 - Detached 8.5m Laneway
 - Detached 12m Laneway
 - Mode 8.5m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m

- Urban Lots**
- Urban Lot Type A
 - Urban Lot Type B
 - Urban Lot Type C & D

Legend

REVISION

J: 06/02/15 minor adjustments requested by CDDP
J: 11/02/15 Surveying and change category of 1 ha lot
K: 15/07/15 new driveway layout and update lot numbering
L: 24/07/15 add transformer sites
M: 06/08/15 Amend Alignments, Roads and Parking
N: 21/08/15 Change Request
O: 28/08/15 Amend Slp 14.35, 43 Park and nearby lots
P: 12/10/15 Minor Changes
Q: 19/12/15 Amend Open Space, Staging, Alignments
R: 04/03/16 Minor Change Application
S: 14/03/16 Minor Changes

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
The boundaries shown on this plan should not be used for final detailed engineers design.

Legend

- General**
- Site Boundary
 - Application Boundary
 - Waterway
 - Riparian Zone
 - Lifestyle Buffer (30m Deep)
 - Blackbutt Forest
 - 30m PMAV Offset to Blackbutt Forest
 - WSF Habitat Protected
 - Potential Sales Office
 - Permissible Multiple Residential (Duplex)
 - Access Easement for Telecommunications Site
 - Proposed Indicative Translink Bus Bay
 - Sewer Pump Station

CLIENT
STOCKLAND

PROJECT
**CALOUNDRA SOUTH
PRECINCT 2**

**OVERALL
STAGING
PLAN**

Date	14 March 2016
Comp By	CC / BM / MD / KH / WW
Checked By	CC
DWG Name	167100-103 CSPPR PRO
Job Reference	167100-21
Local Authority	MINISTER FOR ECONOMIC DEVELOPMENT QLD
Locality	CALOUNDRA SOUTH
Scale	1:2500
Sheet	A1
Plan Ref	167100-110
Rev	S


RPS

RPS Australia East Pty Ltd
ACN 140 292 752
ABN 44 140 292 752
Urban Design
Brisbane Design Studio
455 Brunswick Street
Fortitude Valley QLD 4006
T +61 7 3124 9000
F +61 7 3124 9399
W rpsgroup.com.au

© copyright projects to the extent
indicated. All other rights reserved.

8 APR 2016

MEDQ



Legend

Land Use

- District Centre Commercial
- P-6 State School
- 7-12 State School
- Childcare
- Mixed Use

Open Space

- Pedestrian Link / Buffer (in road reserve)
- Local Linear Park
- District Recreation Park (Linear)
- Town Square (Civic Square / Local Linear Park)
- Neighbourhood Recreation Park
- Drainage Corridors
- Neighbourhood Sports Park
- Major Recreation Park
- Environmental Protection (EPZ)
- Conservation Buffer

32m Deep Lots

- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m
- Large Lots >32m Deep

30m Deep Lots

- SOHO 10m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

28m Deep Lots

- Terrace 5m Laneway
- Terrace 7.5m Laneway
- Terrace 9m Laneway
- Detached 10m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

25m Deep Lots

- Terrace 7.5m
- Terrace 9m
- Detached 8.5m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

Urban Lots

- Urban Lot Type A
- Urban Lot Type B
- Urban Lot Type C & D

Development Controls


- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Indicative 4.8m Wide Driveway
- Indicative 3.5m Wide Driveway
- Alternative 4.8m Wide Driveway
- Indicative Car Park Location

Parking

- Total Visitor Parking Spaces: 161
- Total Dwellings: 287 *

* Excludes Multiple Residential Dwelling Site

Parking Bay Diagram



Lots Potentially Impacted by Road Noise

- ☆ Lots Potentially Impacted By Road Traffic Noise At All Floor Levels
- ★ Lots Potentially Impacted By Road Traffic Noise Above Ground Floor Level

Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107:2000 'Acoustics - Recommended design sound levels and reverberation times for building interiors'.

REVISION
1: 15/02/15 error adjustments requested by DSDP
2: 11/02/15 Surveying and change category of 1 res lot
K: 15/07/15 new driveway layout & update lot numbering
L: 24/07/15 add transformer sites
M: 06/08/15 Amend Allotments, Roads and Parking
N: 21/08/15 Change Request
O: 28/08/15 Amend Stp 14.35.43 Park and nearby lots
P: 12/10/15 Minor Changes
Q: 19/12/15 Amend Open Space, Staging, Allotments
R: 04/03/16 Minor Change Application
S: 14/03/16 Minor Changes
T: 23/03/16 Res driveway changes in Stages 7A & 32

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
Areas have been rounded down to the nearest 5m².
The boundaries shown on this plan should not be used for final detailed engineers design.

Legend

General

- Site Boundary
- Application Boundary
- Neighbourhood Boundary
- Lifestyle Buffer (30m Deep)

- Potential Sales Office
- Permissible Multiple Residential (Duplex)
- Permissible 3 Storey Height Limit
- Proposed Indicative Translink Bus Bay
- Sewer Pump Station

CLIENT

STOCKLAND

PROJECT

CALOUNDRA SOUTH
PRECINCT 2

CENTRAL
NEIGHBOURHOOD
PLAN OF
DEVELOPMENT

Date	23 March 2016
Comp By	CC / BM / MD / KH / WW
Checked By	CC
DWG Name	167100-103 CSPPR PRO
Job Reference	167100-21
Local Authority	MINISTER FOR ECONOMIC DEVELOPMENT QLD
Locality	CALOUNDRA SOUTH
Scale	1:1000
Sheet	A1
Plan Ref	167100-115
Rev	T

RPS

RPS Australia East Pty Ltd
ACN 140 292 762
ABN 44 140 292 762
Urban Design
Brisbane Design Studio
455 Brunswick Street
Fortitude Valley QLD 4006
T +61 7 3124 9900
F +61 7 3124 9399
W rpsgroup.com.au

Legend

General

- Site Boundary
- Application Boundary
- Neighbourhood Boundary
- Lifestyle Buffer (30m Deep)
- Permissible Multiple Residential (Duplex)
- Sewer Pump Station

Land Use

- District Centre Commercial
- P-6 State School
- 7-12 State School
- Childcare
- Emerging Community

Open Space

- Pedestrian Link / Buffer (in road reserve)
- Local Linear Park
- District Recreation Park (Linear)
- Town Square (Civic Square/Local Linear Park)
- Neighbourhood Recreation Park
- Drainage Corridors
- Neighbourhood Sports Park
- Major Recreation Park
- Environmental Protection (EPZ)
- Conservation Buffer

32m Deep Lots

- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m
- Large Lots >32m Deep

30m Deep Lots

- SOHO 10m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

28m Deep Lots

- Terrace 5m Laneeway
- Terrace 7.5m Laneeway
- Terrace 9m Laneeway
- Detached 10m Laneeway
- Detached 12m Laneeway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

25m Deep Lots

- Terrace 7.5m
- Terrace 9m
- Detached 8.5m Laneeway
- Detached 12m Laneeway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

Urban Lots

- Urban Lot Type A
- Urban Lot Type B
- Urban Lot Type C & D

Development Controls

- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Indicative 4.8m Wide Driveway
- Indicative 3.5m Wide Driveway
- Alternative 4.8m Wide Driveway
- Indicative Car Park Location


Parking

Total Visitor Parking Spaces 248
Total Dwellings 419

* Excludes Multiple Residential Dwelling Site

Parking Bay Diagram

Scale 1: 100



Lots Potentially Impacted by Road Noise

- Lots Potentially Impacted by Road Traffic Noise At All Floor Levels
- Lots Potentially Impacted by Road Traffic Noise Above Ground Floor Level

Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107:2000 'Acoustics - Recommended design sound levels and reverberation times for building interiors'.

Notes



All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval. Dimensions have been rounded to the nearest 0.1 metres. Areas have been rounded down to the nearest 5m².

The boundaries shown on this plan should not be used for final detailed engineers design.

PLANS AND DOCUMENTS referred to in the PDA APPROVAL

8 APR 2016

MEDQ






PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

8 APR 2016

MEDQ



Legend

Land Use

- District Centre Commercial
- P-6 State School
- 7-12 State School
- Childcare
- Mixed Use

Open Space

- Pedestrian Link / Buffer (in road reserve)
- Local Linear Park
- District Recreation Park (Linear)
- Town Square (Civic Square / Local Linear Park)
- Neighbourhood Recreation Park
- Drainage Corridors
- Neighbourhood Sports Park
- Major Recreation Park
- Environmental Protection (EPZ)
- EPZ within Major Recreation Park
- Conservation Buffer

32m Deep Lots

- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m
- Large Lots > 32m Deep

30m Deep Lots

- SOHO 10m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

28m Deep Lots

- Terrace 5m Laneway
- Terrace 7.5m Laneway
- Terrace 9m Laneway
- Detached 10m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

25m Deep Lots

- Terrace 7.5m
- Terrace 9m
- Detached 8.5m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

Urban Lots

- Urban Lot Type A
- Urban Lot Type B
- Urban Lot Type C & D

Development Controls

- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Indicative 4.8m Wide Driveway
- Indicative 3.5m Wide Driveway
- Alternative 4.8m Wide Driveway
- Indicative Car Park Location


Parking

Total Visitor Parking Spaces 148
Total Dwellings 264*

* Excludes Multiple Residential Dwelling Site

Parking Bay Diagram

Scale 1: 100



Lots Potentially Impacted by Road Noise

- ☆ Lots Potentially Impacted By Road Traffic Noise At All Floor Levels
- ★ Lots Potentially Impacted By Road Traffic Noise Above Ground Floor Level

Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107:2000 'Acoustics - Recommended design sound levels and reverberation times for building interiors'.

REVISION

1: 06/02/15 error adjustments requested by DSDP

2: 11/02/15 formatting and change category of 1 res lot

3: 15/07/15 new dv layout & update lot numbering

4: 24/07/15 add transformer sites

5: 06/08/15 Amend Allotments, Roads and Parking

6: 21/08/15 Change Request

7: 28/08/15 Amend Slp 14.35.43 Park and nearby lots

8: 12/10/15 Minor Changes

9: 19/12/15 Amend Open Space, Staging, Allotments

10: 04/03/16 Minor Change Application

11: 14/03/16 Minor Changes

Note:

All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.

Dimensions have been rounded to the nearest 0.1 metres.

Areas have been rounded down to the nearest 5m².

The boundaries shown on this plan should not be used for final detailed engineers design.

Legend

General

- Site Boundary
- Application Boundary
- Neighbourhood Boundary
- Lifestyle Buffer (30m Deep)
- Blackbutt Forest
- 30m PMAV Offset to Blackbutt Forest
- Permissible Multiple Residential (Duplex)
- Permissible 3 Storey Height Limit
- Potential Sales Office
- Proposed Indicative Translink Bus Bay
- Sewer Pump Station

CLIENT

STOCKLAND

PROJECT
CALOUNDRA SOUTH
PRECINCT 2

SOUTH-EAST
NEIGHBOURHOOD
PLAN OF
DEVELOPMENT

Date: 14 March 2016
Comp By: CC / BM / MD / KH / WW
Checked By: CC
DWG Name: 167100-103 CSPPR PRO
Job Reference: 167100-21
Local Authority: MINISTER FOR ECONOMIC DEVELOPMENT QLD
Locality: CALOUNDRA SOUTH
Scale: 1:1000 Sheet: A1
Plan Ref: 167100-119 Rev: S

RPS

RPS Australia East Pty Ltd
ACN 140 292 752
ABN 44 140 292 752

Urban Design
Brisbane Design Studio
455 Brunswick Street
Fortitude Valley QLD 4006
T +61 7 3124 9300
F +61 7 3124 9399
W rpsgroup.com.au

© copyright projects the plan
unpublished. All rights reserved.

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

8 APR 2016

MEDQ

Neighbourhood
Recreation Park
80019

90023
56,534 ha



Legend

Land Use

- District Centre Commercial
- P-6 State School
- 7-12 State School
- Childcare
- Mixed Use
- Integrated Tourism Attraction

Open Space

- Pedestrian Link / Buffer (in road reserve)
- Local Linear Park
- District Recreation Park (Linear)
- Town Square (Civic Square / Local Linear Park)
- Neighbourhood Recreation Park
- Drainage Corridors
- Neighbourhood Sports Park
- Major Recreation Park
- Environmental Protection (EPZ)
- EPZ within Major Recreation Park
- Conservation Buffer

32m Deep Lots

- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m
- Large Lots >32m Deep

30m Deep Lots

- SOHO 10m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

28m Deep Lots

- Terrace 5m Laneway
- Terrace 7.5m Laneway
- Terrace 9m Laneway
- Detached 10m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

25m Deep Lots

- Terrace 7.5m
- Terrace 9m
- Detached 8.5m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

Urban Lots

- Urban Lot Type A
- Urban Lot Type B
- Urban Lot Type C & D

Parking

Total Visitor Parking Spaces 54
Total Dwellings 94*

* Excludes Multiple Residential Dwelling Site

Parking Bay Diagram

Scale 1 : 100



Lots Potentially Impacted by

Road Noise

- ☆ Lots Potentially Impacted By Road Traffic Noise At All Floor Levels
- ★ Lots Potentially Impacted By Road Traffic Noise Above Ground Floor Level

Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107-2000 'Acoustics'. Recommended design sound levels and reverberation times for building interiors.



REVISION
1: 06/02/15 error adjustments requested by DSDP
2: 11/02/15 formatting and change category of 1 res lot
K: 15/07/15 new dv layout & update lot numbering
L: 24/07/15 add transformer sites
M: 06/08/15 Amend Allotments, Roads and Parking
N: 21/08/15 Change Request
O: 28/08/15 Amend Slop 14.35.43 Park and nearby lots
P: 12/10/15 Minor Changes
Q: 19/12/15 Amend Open Space, Staging, Allotments
R: 04/03/16 Minor Change Application
S: 14/03/16 Minor Changes

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
Areas have been rounded down to the nearest 5m².
The boundaries shown on this plan should not be used for final detailed engineers design.

Legend

General

- Site Boundary
- Application Boundary
- Neighbourhood Boundary
- Lifestyle Buffer (30m Deep)
- Blackbutt Forest
- 30m PMAV Offset to Blackbutt Forest
- WSF Habitat Protected
- Permissible 3 Storey Height Limit
- Sewer Pump Station

Development Controls

- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Indicative 4.8m Wide Driveway
- Indicative 3.5m Wide Driveway
- Alternative 4.8m Wide Driveway
- Indicative Car Park Location

CLIENT

STOCKLAND

PROJECT

CALOUNDRA SOUTH
PRECINCT 2

POCKET
NEIGHBOURHOOD
PLAN OF
DEVELOPMENT

Date: 14 March 2016

Comp By: CC / BM / MD / KH / WW

Checked By: CC

DWG Name: 167100-103 CSPPR PRO

Job Reference: 167100-21

Local Authority: MINISTER FOR ECONOMIC DEVELOPMENT QLD

Locality: CALOUNDRA SOUTH

Scale: 1:1000

Sheet: A1

Plan Ref: 167100-121

Rev: S


RPS

RPS Australia East Pty Ltd
ACN 140 292 762
ABN 44 140 292 762
Urban Design
Brisbane Design Studio
455 Brunswick Street
Fortitude Valley QLD 4006
T +61 7 3124 9300
F +61 7 3124 9399
W rpsgroup.com.au

© copyright reserved to the plan
owner. All rights reserved.

8 APR 2016

MEDQ



Legend

Land Use

- District Centre Commercial
- P-6 State School
- 7-12 State School
- Childcare
- Mixed Use

Open Space

- Pedestrian Link / Buffer (in road reserve)
- Local Linear Park
- District Recreation Park (Linear)
- Town Square (Civic Square / Local Linear Park)
- Neighbourhood Recreation Park
- Drainage Corridors
- Neighbourhood Sports Park
- Major Recreation Park
- Environmental Protection (EPZ)
- Conservation Buffer

32m Deep Lots

- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m
- Large Lots >32m Deep

30m Deep Lots

- SOHO 10m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

28m Deep Lots

- Terrace 5m Laneway
- Terrace 7.5m Laneway
- Terrace 9m Laneway
- Detached 10m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

25m Deep Lots

- Terrace 7.5m
- Terrace 9m
- Detached 8.5m Laneway
- Detached 12m Laneway
- Mode 8.5m
- Villa 10m
- Premium Villa 12.5m
- Courtyard 14m
- Premium Traditional 18m

Urban Lots

- Urban Lot Type A
- Urban Lot Type B
- Urban Lot Type C & D

Development Controls

- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Indicative 4.8m Wide Driveway
- Indicative 3.5m Wide Driveway
- Alternative 4.8m Wide Driveway
- Indicative Car Park Location

Parking

Total Visitor Parking Spaces 108
Total Dwellings 198

* Excludes Multiple Residential Dwelling Site

Parking Bay Diagram

Scale 1: 100



Lots Potentially Impacted by Road Noise

- Lots Potentially Impacted By Road Traffic Noise At All Floor Levels
- Lots Potentially Impacted By Road Traffic Noise Above Ground Floor Level

Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107:2000 'Acoustics - Recommended design sound levels and reverberation times for building interiors'.

REVISION
1: 06/02/15 error adjustments requested by ODGP
2: 11/02/15 formatting and change category of 1 res lot
3: 15/07/15 new driveway layout & update lot numbering
4: 24/07/15 add transformer sites
5: 06/08/15 Amend Allotments, Roads and Parking
6: 21/08/15 Change Request
7: 28/08/15 Amend Slop 14.35.43 Park and nearby lots
8: 12/10/15 Minor Changes
9: 15/12/15 Amend Open Space, Staging, Allotments
10: 04/03/16 Minor Change Application
11: 14/03/16 Minor Changes

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
Areas have been rounded down to the nearest 5m².
The boundaries shown on this plan should not be used for final detailed engineers design.

Legend

General

- Site Boundary
- Application Boundary
- Neighbourhood Boundary
- Waterway
- Riparian Zone
- Lifestyle Buffer (30m Deep)
- WSF Habitat Protected
- Permissible Multiple Residential (Duplex)
- Permissible 3 Storey Height Limit
- Sewer Pump Station

CLIENT

STOCKLAND

PROJECT

CALOUNDRA SOUTH
PRECINCT 2

SOUTHERN
NEIGHBOURHOOD
PLAN OF
DEVELOPMENT

Date 14 March 2016

Comp By CC / BM / MD / KH / WW

Checked By CC

DWG Name 167100-103 CSPPR PRO

Job Reference 167100-21

Local Authority MINISTER FOR ECONOMIC
DEVELOPMENT OLD

Locality CALOUNDRA SOUTH


Scale 1:1000 Sheet A1

Plan Ref 167100-123 Rev S


RPS

RPS Australia East Pty Ltd
ACN 140 292 762
ABN 44 140 292 762
Urban Design
Brisbane Design Studio
455 Brunswick Street
Fortitude Valley QLD 4006
T +61 7 3124 9300
F +61 7 3124 9399
W rpsgroup.com.au

© copyright reserved to the plan
author. All rights reserved.



PLANS AND DOCUMENTS
referred to in the POA APPROVAL
8 APR 2016
MEDQ



- Legend**
- General**
- Site Boundary
 - Application Boundary
 - Neighbourhood Boundary
 - Waterway
 - Riparian Zone
 - Lifestyle Buffer (30m Deep)
 - Permissible Multiple Residential (Duplex)
 - Proposed Indicative Translink Bus Bay
 - Sewer Pump Station
- Land Use**
- District Centre Commercial
 - P-6 State School
 - 7-12 State School
 - Childcare
 - Mixed Use
- Open Space**
- Pedestrian Link / Buffer (in road reserve)
 - Local Linear Park
 - District Recreation Park (Linear)
 - Town Square (Civic Square/Local Linear Park)
 - Neighbourhood Recreation Park
 - Drainage Corridors
 - Neighbourhood Sports Park
 - Major Recreation Park
 - Environmental Protection (EPZ)
 - Conservation Buffer
- 32m Deep Lots**
- Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m
 - Large Lots >32m Deep
- 30m Deep Lots**
- SOHO 10m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m
- 28m Deep Lots**
- Terrace 5m Laneway
 - Terrace 7.5m Laneway
 - Terrace 9m Laneway
 - Detached 10m Laneway
 - Detached 12m Laneway
 - Mode 8.5m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m
- 25m Deep Lots**
- Terrace 7.5m
 - Terrace 9m
 - Detached 8.5m Laneway
 - Detached 12m Laneway
 - Mode 8.5m
 - Villa 10m
 - Premium Villa 12.5m
 - Courtyard 14m
 - Premium Traditional 18m
- Urban Lots**
- Urban Lot Type A
 - Urban Lot Type B
 - Urban Lot Type C & D
- Development Controls**
- Recommended Built to Boundary Wall
 - Optional Built to Boundary Wall
 - Indicative 4.8m Wide Driveway
 - Indicative 3.5m Wide Driveway
 - Alternative 4.8m Wide Driveway
 - Indicative Car Park Location
- Parking**
- Total Visitor Parking Spaces 172
Total Dwellings 298*
- * Excludes Multiple Residential Dwelling Site
- Parking Bay Diagram**
Scale 1 : 100
- Lots Potentially Impacted by Road Noise**
- ☆ Lots Potentially Impacted By Road Traffic Noise At All Floor Levels
 - ★ Lots Potentially Impacted By Road Traffic Noise Above Ground Floor Level
- Note: On lots marked on plan as potentially impacted by road traffic noise, dwellings must be designed such that internal noise levels comply with AS/NZS2107-2000 'Acoustics - Recommended design sound levels and reverberation times for building interiors'.

<div>REVISION</div> <div>I: 06/02/15 minor adjustments requested by DSDP</div> <div>J: 11/02/15 finalising and change category of 1 res lot</div> <div>K: 15/07/15 new dv layout & update lot numbering</div> <div>L: 24/07/15 add transformer sites</div> <div>M: 06/08/15 Amend Allotments, Roads and Parking</div> <div>N: 21/09/15 Change Request</div> <div>O: 28/09/15 Amend Stp 14,35,43 Park and nearby lots</div> <div>P: 12/10/15 Minor Changes</div> <div>Q: 15/12/15 Amend Open Space, Staging, Allotments</div> <div>R: 04/02/16 Minor Change Application</div> <div>S: 14/03/16 Minor Changes</div>	<div>PROJECT</div> <div>CALOUNDRA SOUTH</div> <div>PRECINCT 2</div>		<div>CLIENT</div> <div>STOCKLAND</div>		<div><div><div>RPS</div></div><div><div>RPS Australia East Pty Ltd</div><div>ACN 140 292 762</div><div>ABN 44 140 292 762</div></div></div> <div><div>Urban Design</div><div>Brisbane Design Studio</div><div>455 Brunswick Street</div><div>Fortitude Valley QLD 4006</div></div> <div><div>T+61 7 3124 9300</div><div>F+61 7 3124 9399</div><div>W rpsgroup.com.au</div></div>		
	<div>Job Ref.</div> <div>167100-21</div>	<div>Date</div> <div>14 March 2016</div>	<div>SOUTH WEST</div> <div>NEIGHBOURHOOD</div> <div>PLAN OF DEVELOPMENT</div>				
	<div>Comp By:</div> <div>CC / BM / MD / KH</div>	<div>DWG Name:</div> <div>167100-103 CSP2 PRO</div>					
	<div>Checked By:</div> <div>CC</div>	<div>Locality</div> <div>CALOUNDRA SOUTH</div>					
	<div>Local Authority</div> <div>MINISTER FOR ECONOMIC DEVELOPMENT QLD</div>						
<div>Scale</div> <div>1:1000</div>					<div>Sheet</div> <div>A1</div>	<div>Plan Ref</div> <div>167100-125</div>	<div>Rev</div> <div>S</div>

[illegible]

E Series

Max. 15m in Length

20 - 32m

0.9

1.5

8.1

19.22 & 25

6.6

4.5

2.4




Ø3

Street





Technical drawing of a D Series manhole. The drawing shows a top-down view of the manhole structure. The main body is orange and labeled "D Series". It has a width of 10.5m and a height of 11.5m. The manhole is set within a larger rectangular frame with dimensions 1m by 1m. The manhole is surrounded by a 1.5m wide area. The manhole is connected to a street via a 4.5m wide opening. The manhole is labeled "Max. 15m in Length" and "20 - 32m". The manhole is shown with a cross-section of the street and a cross-section of the manhole structure.

Technical drawing of a 'C Series' bus stop shelter. The drawing shows a yellow rectangular shelter with a dashed red border. Dimensions include a total width of 20-32m, a shelter width of 12m, and a shelter depth of 13m. A side view shows a height of 1.5m and a depth of 4.5m. A cross-section shows a width of 1m and a depth of 2.4m. The shelter is labeled 'C Series' and 'Max. 15m in Length'. A street is shown at the bottom.


[illegible]

-  Garage location
 Single garage for single storey dwelling
 Double garage when 2 storey dwelling
 Indicative driveway location


Mode Allotment 10m – <11.5m Wide
Villa Allotment 11.5m – <14m Wide
Premium Villa Allotment 14m – <15.5m Wide




Courtyard Allotment 15.5m – <18.5m Wide



Premium Traditional Allotment 18.5m+ Wide



Large Allotment 18.5m+ Wide



Legend

- Maximum Building Envelope
- Building Setback Dimensions
- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Garage Setback to Front Boundary

- Corner setback
- Stockland product envelope
- Building product dimensions
- Preferred private open space location 15m² min. with min. dimension of 3m
- Alternative location for private open space

- Garage location
- Single garage for single storey dwelling
Double garage when 2 storey dwelling
- Indicative driveway location
- Alternative garage location on secondary street: double garage permissible

Plan of Development Table	Mode Allotments		Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Traditional and Large Lots Allotments		Multiple Residential Allotments (Duplex)	
	8.5m – <10.0m Wide		10.0m – <12.5m Wide		12.5m – <14m Wide		14m – <18m Wide		18m & above Wide			
	Ground Floor	Upper Floors	Ground Floor	Upper Floors	Ground Floor	Upper Floors	Ground Floor	Upper Floors	Ground Floor	Upper Floors	Ground Floor	Upper Floors
Front/Primary Frontage	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4
Garage	5.5m for single or tandem garages & 4.5m for double garages	n/a	5.5m for single or tandem garages & 4.5m for double garages	n/a	4.5	n/a	4.5	n/a	4.5	n/a	4.5	n/a
Rear	1.5	3.0	1.5	3.0	1.5	3.0	1.5	3.0	1.5 ^	3.0	1.0*	1.0*
Side - General Lots									^ 3.0m for large lots		* Second side setback as no rear setback applies.	
Built to Boundary	0.0	1.0	0.0	1.0	0.0	1.0	0.0	1.0	0.0	1.0	0.0	1.0
Non Built to Boundary	0.9	0.9	0.9	0.9	1.0	1.0	1.0	1.0	1.5	1.5	1.0	1.0
Corner Lots - Secondary Frontage	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4	2.4
Garage and On-site Car Parking												
On site parking requirements (minimum)	1 space to be covered and enclosed		1 space to be covered and enclosed		1 space to be covered and enclosed		1 space to be covered and enclosed		1 space to be covered and enclosed		1 space per dwelling to be covered and enclosed	
Garage location	Single Garages (up to 3.5m in width) or tandem garages are acceptable.		Single Garages (up to 4.5m~ in width) or tandem garages are acceptable.		Single, tandem or double garage acceptable.		Single, tandem or double garage acceptable.		Single, tandem or double garage acceptable.		Single, tandem or double garage acceptable.	
	Double Garages (greater than 3.5m in width) are only permitted for 2 storey dwellings.		Double Garages (greater than 4.5m~ in width) are only permitted for 2 storey dwellings.		Garages are to be located along the built to boundary wall		Garages are to be located along the built to boundary wall		Garages are to be located along the western or southern boundary where appropriate.		Garages are to be located along the western or southern boundary where appropriate.	
Site Cover (maximum)	75%		60%		60%		60%		60%		75%	

Notes

General

- All development inclusive of Single and Multiple Residential Allotments (Duplex) is to be undertaken in accordance with the Development Approval.
- Building setbacks and built-to-boundary wall locations shown are subject to future proposed easements and/or underground services.
- Maximum building height is 3 storeys for dwellings where permitted in the Plan of Development, 2 storeys (9m) otherwise. Rooftop terraces are defined as a 'storey'.

Setbacks

- A corner lot, for the purposes of determining setbacks, is a lot that adjoins the intersection of two streets (collector, access street or access place) or a street and a lane. This excludes those lots that abut a shared access driveway or a pedestrian connection/threshold and therefore in these cases a secondary frontage setback **does not apply**.
- Setbacks are as per the Plan of Development Table unless otherwise specified. In the case of Courtyard, Traditional and Premium Traditional Corner Lots, an additional setback from the street corner is applicable. The setback applies to any building or structure greater than 2m high. The setback is measured as the line that joins the points on the front and side street boundaries of the lot that are located 9m back from the point of intersection of these two boundaries.
- Corner lots are interpreted as having two front boundaries and two side boundaries for the purposes of determining building setbacks (ie. no rear boundary setback applies).
- Built to Boundary walls are recommended where road frontage widths are less than 15 metres. Built to Boundary walls are optional for lots with road frontage widths equal to, or in excess of 11 metres. Where Built to Boundary walls are not adopted side setbacks for non-built to boundary walls apply.
- Built to Boundary walls are to have a maximum length of 15 metres and a maximum height of 3.5 metres.
- Boundary setbacks are measured to the wall of the structure. Eaves should not encroach closer than 450mm to the lot boundary except in the case of:
 - The Primary Street Frontage where eaves should not be closer than 2000mm;
 - Walls that are Built to Boundary.
- Upper floor setbacks must not exceed the minimum ground floor setbacks.

- Roofed gatehouses and arches are permitted within the front setback (and the secondary frontage for corner lots) provided they meet the requirements of the QDC, having a:
 - Maximum area of 4m²; and
 - Not more than 2m wide elevation to the street; and
 - Not more than 3m in height.

Site Cover and Amenity

- Site cover for each lot is not to exceed the maximum specified for the lot, including Multiple Residential Allotments (Duplex), unless the dwelling is in accordance with approved house plans and where appropriate building staging and construction techniques have been demonstrated.
- Private amenity space, must be provided and is not less than 15m² with a minimum dimension of 3.0m and is directly accessible from a ground floor living area.

Privacy & Overlooking

- Buildings must be sited and designed to provide adequate visual privacy for neighbours:
 - Where the distance separating a window or balcony of an adjoining dwelling from the side or rear boundary is less than 1.5 m:
 - a permanent window and a balcony has a window/balcony screen extending across the line of sight from the sill to at least 1.5m above the adjacent floor level; or
 - a window has a sill height more than 1.5m above the adjacent floor level; or
 - a window has obscure glazing below 1.5m; where: Window and Window/Balcony Screen has the same meaning as in the Queensland Development Code.

Fencing

15. For Detached lots:

Fencing along primary street frontages must be either 50% transparent or max. 1.2m high. Fencing to secondary street frontages may be screen fencing max. 1.8m high and extend up to the front building line (main facade).

For Multiple Residential (Duplex Lots):

Fencing along primary and secondary street frontages must be either 50% transparent or max. 1.2m high.

Parking and Driveways

- For all allotments the following applies:
 - Double garages will not be permitted on a single storey dwelling, on a lot less than 12.5m wide;
 - Double garages may be permitted on a lot 7.5m or wider and less than 12.5m wide where the dwelling is more than one storey in height, and where:
 - the garage is setback at least 1m behind the main facade, excluding balconies, of the dwelling AND
 - the garage doors are articulated, comprise a mix of materials and colours, or are staggered.
 - Double garages are permitted on any corner lot if the garage fronts the secondary street frontage as shown in the setback diagrams for detached corner allotments and minimum setbacks (including garage setbacks) can be met.
 - The maximum width of a driveway at the lot boundary & where crossing the verge:
 - serving a double garage shall be 4.8m; and
 - serving a single garage shall be 3.0m.
- Parking spaces on driveways do not have to comply with gradients in AS2890.
- A maximum of one driveway per lot is permitted (2 for duplex allotments).
- Driveways should avoid on-street works such as dedicated on-street parking bays, drainage pits and service pillars.
- The minimum distance of a driveway from an intersection of one street with another street shall be 6.0 metres.
- The minimum distance between driveways on the same duplex lot shall be 3.0 metres at the boundary.

Rainwater Tanks

- All detached dwellings must have a min 5000 litre rainwater tank. All multiple residential dwellings (duplex and triplex) must have a min 3000 litre rainwater tank per dwelling. All tanks to residential dwellings must collect a minimum 50% roof area capture. All tanks must supply water to toilets, laundry, hot water and have a connection for external usage and must have a backup supply from the main potable water system.

Definitions

Site Cover - the total area of the roof of the dwelling expressed as a percentage of the lot area, but which excludes eave overhangs.

Detached and Multiple Residential Allotments (Duplex) Notes & Tables

Notes

General

- All development is to be undertaken in accordance with the Development Approval.
- Building setbacks and built-to-boundary wall locations shown are subject to future proposed easements and/or underground services.
- Maximum building height is 3 storeys for all dwellings where permitted in the Plan of Development, and 2 storeys (9m) otherwise. Rooftop terraces are defined as a 'storey'.

Setbacks

- Setbacks are as per the Plan of Development Table unless otherwise specified.
- Where Built to Boundary walls are not adopted side setbacks for non-built to boundary walls apply.
- A corner lot, for the purposes of determining setbacks, is a lot that adjoins the intersection of two streets (collector, access street or access place) or a street and a lane. This excludes those lots that abut a shared access driveway or a pedestrian connection/threshold and therefore in these cases a secondary street setback **does not apply**.
- Built to Boundary wall shall be no more than 85% of the length of the boundary and may be higher than 3.5 metres where in accordance with approved house plans and where appropriate building staging and construction techniques are demonstrated.
- Boundary setbacks are measured to the wall of the structure. Eaves should not encroach closer than 450mm to the lot boundary except in the case of:
 - The Primary Street Frontage where eaves should not be closer than 1500mm;
 - Terrace Allotments where the Built to Boundary wall may be a common wall or no setback is required; and
 - Walls that are Built to Boundary.
- Upper floor setbacks must not exceed the minimum ground floor setbacks, including roof top terraces.
- Roofed gatehouses and arches are permitted within the front setback (and the secondary frontage for corner lots) provided they meet the requirements of the QDC, having a:
 - Maximum area of 4m²; and
 - Not more than 2m wide elevation to the street; and
 - Not more than 3m in height.

Site Cover and Amenity

- Site cover for each lot is not to exceed 75% of the lot, unless the dwelling is in accordance with approved house plans and where appropriate building staging and construction techniques have been demonstrated.
- Private amenity space, must be provided and is not less than 15m² with a minimum dimension of 3.0m and is directly accessible from a ground floor living area.

Privacy & Overlooking

- Buildings must be sited and designed to provide adequate visual privacy for neighbours:
 - Where the distance separating a window or balcony of an adjoining dwelling from the side or rear boundary is less than 1.5 m:
 - a permanent window and a balcony has a window/balcony screen extending across the line of sight from the sill to at least 1.5m above the adjacent floor level; or
 - a window has a sill height more than 1.5m above the adjacent floor level; or
 - a window has obscure glazing below 1.5m; where: Window and Window/Balcony Screen has the same meaning as in the Queensland Development Code.

Fencing

- Fencing along the primary street frontage must be either 50% transparent or max. 1.2m high. Fencing to secondary street frontages may be screen fencing up to 1.8m high up to the front building line (main facade).

Parking and Driveways

- For all allotments the following applies:
 - Double garages will not be permitted on a single storey dwelling;
 - Double garages may be permitted where the dwelling is more than one storey in height, and where:
 - the garage is setback at least 1m behind the main facade, excluding balconies, of the dwelling AND
 - the garage doors are articulated, comprise a mix of materials and colours, or are staggered.
 - The maximum width of a driveway at the lot boundary & where crossing the verge:
 - serving a double garage shall be 4.8m; and
 - serving a single garage shall be 3.0m.
- Parking spaces on driveways do not have to comply with gradients in AS2890.
- A maximum of one driveway per dwelling is permitted
- Driveways should avoid on-street works such as dedicated on-street parking bays, drainage pits and service pillars.
- The minimum distance of a driveway from an intersection of one street with another street shall be 6.0 metres.

Access Deeds

- Access Deeds are required to be established on all dwellings where there are adjoining built to boundary walls. These deeds will permit periodic maintenance access onto the roof of the dwelling on the adjoining lot, and permit roof water and waste to be deposited from time to time on to the roof.

Rainwater Tanks


- All attached dwellings (including urban, terraces, laneway terrace and duplex dwellings) must have a min 3000 litre rainwater tank. All tanks to residential dwellings must collect a minimum 50% roof area capture. All tanks must supply water to toilets, laundry, hot water and have a connection for external usage and must have a backup supply from the main potable water system.

Definitions


Site Cover - the total area of the roof of the dwelling expressed as a percentage of the lot area, but which excludes eave overhangs

Plan of Development Table	Terrace Allotments	
	7.5m – <10m Wide	
	Ground Floor	First Floor
Front/Primary Frontage	2.0	2.0
Garage	5.5m for single or tandem garages & 4.5m for double garages	n/a
Rear	1.5	1.5
Side - General Lots		
Built to Boundary	0.0	0.0
Non Built to Boundary	0.9	0.9
Corner Lots - Secondary Frontage	2.0	2.0
Garage and On-site Car Parking		
On site parking requirements (minimum)	1 space to be covered and enclosed	
	Single or tandem garage acceptable.	
	Double garages are only permitted on two storey dwellings.	
	Garages are to be located along the built to boundary wall.	
Garage location		
Site Cover (maximum)	75%	

Terrace Allotment 7.5m – <10m Wide



Corner Terrace Allotment 10m – <11.5m Wide



Legend

- Maximum Building Envelope
- Building Setback Dimensions
- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall (where permitted on Plan of Development)
- Garage Setback to Front Boundary
- Stockland product envelope
- Building product dimensions
- Preferred private open space location 15m² min. with min. dimension of 3m
- Alternative location for private open space
- Garage location
- Single garage for single storey dwelling Double garage when 2 storey dwelling
- Indicative driveway location
- Preferred letterbox location


SCALE 1 : 500 @ A4

Terrace Allotments Diagrams


Caloundra South - Precinct 2 Stockland

Loft Dwellings on Laneway

- ground floor



- upper floors



Legend

- Indicative Garage
- Setback Dimensions
- Indicative Driveway Location
- Preferred Private Open Space Location 15m² min. with min. dimension of 3m
- Maximum Building Envelope
- Maximum Building Envelope - upper floors
- Garage Setback to Front Boundary
- Preferred Location of Bin Storage
- Preferred Location of Bin Collection
- Preferred Letterbox Location
- Entrance to Main Dwelling
- Entrance to Loft Dwelling

SCALE 1 : 500 @ A4



Notes

General

- All development is to be undertaken in accordance with the Development Approval.
- Building setbacks and built-to-boundary wall locations shown are subject to future proposed easements and/or underground services.
- Maximum building height is 3 storeys for dwellings where permitted in the Plan of Development, and 2 storeys (9m) otherwise. Rooftop terraces are defined as a 'storey'.

Setbacks

- Setbacks are as per the Plan of Development Table unless otherwise specified.
- Built to Boundary Walls:
 - Built to boundary wall dimensions are limited by the applicable boundary setbacks and building height limit. Building plans and details of appropriate development staging and construction methods must be submitted for approval;
 - where not adopted, the standard setbacks in the Plan of Development Table apply.
- Boundary setbacks are measured to the wall of the structure. Eaves should not encroach closer than 450mm to the lot boundary except in the case of:
 - The Primary Street/Park Frontage where eaves should not be closer than 1500mm;
 - Terrace Allotments where the Built to Boundary wall may be a common wall or no setback is required; and
 - Walls that are Built to Boundary.
- Upper floor setbacks must not exceed the minimum ground floor setbacks (including rooftop terraces).
- Privacy & Overlooking: Buildings must be sited and designed to provide adequate visual privacy for neighbouring dwellings. Where the distance separating a window or balcony of an adjoining dwelling from the side or rear boundary is less than 1.5 m:
 - a permanent window and a balcony has a window/balcony screen extending across the line of sight from the sill to at least 1.5m above the adjacent floor level; or
 - a window has a sill height more than 1.5m above the adjacent floor level; or
 - a window has obscure glazing below 1.5m;
 where: Window and Window/Balcony Screen has the same meaning as in the Queensland Development Code.
- Where loft dwellings are built adjacent the laneway, the design of windows, balconies and other amenity spaces shall be located and adequately screened to avoid overlooking of and from loft apartments/dwellings on the opposite side of the laneway.
- Roofed gatehouses and arches are permitted within the front setback (and the secondary frontage for corner lots) provided they meet the requirements of the QDC, having a:
 - Maximum area of 4m²; and
 - Not more than 2m wide elevation to the street; and
 - Not more than 3m in height.

Site Cover and Amenity

- Site cover for each lot is not to exceed 85% of the lot, unless the dwelling is in accordance with approved house plans and where appropriate building staging and construction techniques have been demonstrated.
- Private amenity space, must be provided and is not less than 15m² with a minimum dimension of 3.0m and is directly accessible from a ground floor living area. For loft dwellings built adjacent the laneway this amenity space may be roofed and may be provided as a balcony not less than 9m² with a minimum dimension of 1.5m.

Fencing, Letterboxes, Parking and Driveways

- Fencing along street and park frontages must be either 50% transparent or max. 1.2m high. Fencing to the lane may be screen fencing to 1.8m high.
- Letterboxes for the main dwelling shall be located on the primary street or park frontage and not in the laneway. Letterboxes for loft apartments on corner allotments shall be located on the secondary street frontage and not in the laneway. Letterboxes for loft apartments on other lots (mid laneway) may be located on the lane generally as shown in the Loft dwelling on Laneway diagrams.
- Standard allotments adjoining a laneway must have their garage fronting the laneway, comply with the setbacks, and have fencing to the laneway in accordance with that shown in the laneway terrace diagram.
- Parking spaces on driveways do not have to comply with gradients in AS2890.
- A maximum of one driveway per dwelling is permitted which may be shared where there is more than 1 dwelling on a lot.

- Driveways should have the minimum width required to facilitate vehicle access, in order to maintain space between driveways, pathways and any bin storage areas for amenity planting.
- Driveways should avoid on-street works such as dedicated on-street parking bays, drainage pits and service pillars.
- The minimum distance of a driveway from an intersection of one street with another street shall be 6.0 metres.

Loft Dwellings

- Loft dwellings (a self contained dwelling generally with single garage constructed adjacent to the laneway and above the garaging on that allotment) may be constructed on laneway terrace allotments.
- The access, parking, entry, letterbox and rubbish storage and collection shall be generally as shown in the diagrams: Loft Dwellings on Laneway, and Laneway Interface, in this PoD.
- To ensure passive surveillance of the laneway, loft dwellings shall have windows, balconies/verandahs overlooking the lane where requirements for privacy/overlooking can be maintained.

Laneway Interface

- The relationship of garages to the laneway and bin storage areas shall be generally as shown in the diagrams: Laneway Terrace Allotment and Loft Dwellings on Laneway, in this PoD.

Access Deeds

- Access Deeds are required to be established on all dwellings where there are adjoining built to boundary or parti walls. These deeds will permit periodic maintenance access on to the roof of the dwelling on the adjoining lot, and permit roof water and waste to be deposited from time to time on to the roof.

Rainwater Tanks

- All dwellings must have a min 3000 litre rainwater tank. All tanks to residential dwellings must collect a minimum 50% roof area capture. All tanks must supply water to toilets, laundry, hot water and have a connection for external usage and must have a backup supply from the main potable water system.

Definitions

- Site Cover** - the total area of the roof of the dwelling expressed as a percentage of the lot area, but which excludes eave overhangs

Plan of Development Table	Laneway Terrace & Detached Laneway Allotments	
	5m – <10m Wide	
	Ground Floor	First Floor
Front/Primary Frontage	2.0	2.0
Garage	0.5	n/a
Rear	0.5	0.0
Side - General Lots		
Built to Boundary	0.0	0.0
Non Built to Boundary	0.9	0.9
Corner Lots - Secondary Frontage	1.5	1.5
Garage and On-site Car Parking		
On site parking requirements (minimum)	1 space to be covered and enclosed	
Garage location	Single, tandem or double garage acceptable.	
	Garages are to be located along the built to boundary wall.	
Site Cover (maximum)	85%	


Sheet 1 of 3

Laneway Terrace and Detached Laneway Allotment Diagrams

Caloundra South - Precinct 2

Stockland


Laneway Terrace Allotment Terrace onto park or street 5m – 10m+ Wide



Legend

- Indicative Garage
- Garage Location
- Building Product Dimensions
- Setback Dimensions
- Indicative Driveway Location
- Preferred Private Open Space Location
15m² min. with min. dimension of 3m
- Alternative Private Open Space Location
as internal courtyard
- Single Garage for Single Storey Dwelling
Double Garage when 2 Storey Dwelling Only
- Maximum Building Envelope - Ground Floor
- Maximum Building Envelope - Upper Floors
- Recommended Built to Boundary Wall
- Garage Setback to Front Boundary
- Stockland Product Type Envelope
- Preferred Location of Bin Storage
- Preferred Location of Bin Collection
- Preferred Letterbox Location
- Screen Fence to Bins
- Low fencing 1.2-1.4m high
- Screen fencing up to 1.8m high

Laneway Interface



Sheet 2 of 3

Laneway Terrace Allotments Diagrams

Caloundra South - Precinct 2

Stockland




SCALE 1 : 500 @ A4



Detached Laneway Terrace Allotment

Terrace onto park or street

8.5m – 12m+ Wide



Legend

- Indicative Garage
- Garage Location
- Building Product Dimensions
- Setback Dimensions
- Indicative Driveway Location
- Preferred Private Open Space Location
15m² min. with min. dimension of 3m
- Alternative Private Open Space Location
as internal courtyard
- Single Garage for Single Storey Dwelling
Double Garage when 2 Storey Dwelling Only
- Maximum Building Envelope - Ground Floor
- Maximum Building Envelope - Upper Floors
- Recommended Built to Boundary Wall
- Garage Setback to Front Boundary
- Stockland Product Type Envelope
- Preferred Letterbox Location
- Screen Fence to Bins
- Low fencing 1.2-1.4m high
- Screen fencing up to 1.8m high

Development Controls

General

- All development is to be undertaken in accordance with the Development Approval.
- All building setbacks and built to boundary walls are subject to service easements existing and proposed.
- Maximum building height is 2 storeys (9m) for all dwellings. Rooftop terraces are defined as a 'storey'.

Setbacks

- Setbacks are as per the Plan of Development Table, unless dimensioned otherwise on plan.
- Setbacks are measured to the wall of the building or structure. Eaves may extend into the side and rear setbacks up to 450mm from the property boundary. Eaves may extend up to the street boundary for Type A and B Urban Lots and 2000mm for Type C and D Urban Lots.
- Upper floor setbacks must be in accordance with minimum ground floor setbacks.

Built to Boundary Walls:

- Built to boundary wall dimensions are limited by the boundary setbacks and building height limit. Building plans and details of appropriate development staging and construction methods must be submitted for approval;
 - where not adopted, the setbacks for non built to boundary walls in the Plan of Development Table apply.
- Roofed gatehouses and arches are permitted within the front setback (and the secondary frontage for corner lots) provided they meet the requirements of the QDC, having a:
 - Maximum area of 4m²; and
 - Not more than 2m wide elevation to the street; and
 - Not more than 3m in height.

Privacy & Overlooking

- Buildings must be sited and designed to provide adequate visual privacy for neighbours:
 - Where the distance separating a window or balcony of an adjoining dwelling from the side or rear boundary is less than 1.5 m:
 - a permanent window and a balcony has a window/balcony screen extending across the line of sight from the sill to at least 1.5m above the adjacent floor level; or
 - a window has a sill height more than 1.5m above the adjacent floor level; or
 - a window has obscure glazing below 1.5m; where: Window and Window/Balcony Screen has the same meaning as in the Queensland Development Code.

Parking and Driveways

- A maximum of one driveway is permitted per lot.
- Driveways are to have the following widths:
 - single driveway: maximum 3.5m;
 - Shared double driveways are mandatory where shown on plan.
- Driveways are to avoid on-street works such as: dedicated parking bays, drainage inlets, service pillars, street planting beds and bio-retention areas.
- The minimum distance between a driveway and street intersection is 6.0m.
- Parking spaces on driveways do not have to comply with gradients in AS2890.

Site Cover and Amenity

- Site cover for each lot is not to exceed that shown in the Plan of Development table except where the dwelling is in accordance with approved house plans and where appropriate building staging and construction techniques have been demonstrated.
- Private open space may be roofed and must meet the following requirements:
 - Type A: 6m² at ground level;
 - Type B: 9m² at ground level;
 - Type C & D: 12m² at ground level.

Fencing

- Fencing along the street frontage may be up to 1.5m to provide appropriate privacy.

Access Deeds

- Access Deeds are required to be established on all dwellings where there are adjoining built to boundary walls. These deeds will permit periodic maintenance access on to the roof of the dwelling on the adjoining lot, and permit roof water and waste to be deposited from time to time on to the roof.


Rainwater Tanks

- All dwellings must have a min 3000 litre rainwater tank. All tanks to residential dwellings must collect a minimum 50% roof area capture. All tanks must supply water to toilets, laundry, hot water and have a connection for external usage and must have a backup supply from the main potable water system.

Definitions

Site Cover - the total area of the roof of the dwelling expressed as a percentage of the lot area, but which excludes eave overhangs.

Urban Allotments - standard



Plan of Development Table	Urban Allotments Type A & B		Urban Allotments Type C & D	
	Ground Floor	First Floor	Ground Floor	First Floor
Front/Primary Frontage	0.2	0.2	2.4	2.4
Garage	0.5	n/a	4.5	n/a
Rear	0.0	0.0	1.5	1.5
Side - General Lots				
Built to Boundary	0.0	0.0	0.0	0.0
Non Built to Boundary	0.9	0.9	0.9	0.9
Corner Lots - Secondary Frontage	as shown	as shown	1.5	1.5
Garage and On-site Car Parking				
On site parking requirements (minimum)	1 space to be covered and enclosed Single or tandem garage acceptable. Double garages are not permitted. Garages are to be located along the built to boundary wall.		1 space to be covered and enclosed Single or tandem garage acceptable. Double garages are not permitted. Garages are to be located along the built to boundary wall.	
Site Cover (maximum)	85%		85%	

Legend

- Maximum building envelope
- Recommended built to boundary wall
- Garage setback to front boundary
- Garage location
- Building envelope dimensions
- Setback dimensions
- Indicative driveway location

Development Control Notes

- General**
- All development is to be undertaken in accordance with the Development Approval.
 - Building setbacks and built-to-boundary wall locations shown are subject to future proposed easements and/or underground services.
 - Maximum building height is:
 - 3 storeys for the residential component including where constructed above the business/shop component (3 storeys in total);
 - 2 storeys for the business/shop component where no residential floor area is built above.The residential component must be a minimum of two storeys at the residential street frontage. Third storey floor area may not exceed 40% of the total lot area.

- Setbacks**
- Setbacks are as per the Plan of Development Table unless otherwise specified.
 - Built to boundary wall dimensions are limited by the applicable boundary setbacks and building height limit. Building plans and details of appropriate development staging and construction methods must be submitted for approval.
 - Where Built to Boundary walls are not adopted side setbacks for non-built to boundary walls apply.
 - Boundary setbacks are measured to the wall of the structure. Eaves should not encroach closer than 450mm to the lot boundary except in the case of:
 - The Residential Street Frontage where eaves should not be closer than 2000mm;
 - Side boundary setback on lot 4 (to the shared access driveway) where eaves should not be closer than 1500mm;
 - where the Built to Boundary wall may be a common wall or no setback is required; and
 - Walls that are Built to Boundary.
 - Upper floor setbacks must not exceed the minimum ground floor setbacks, including roof top terraces.
 - Roofed gatehouses and arches are permitted within the boundary setback of residential frontage of the lot provided they meet the requirements of the QDC, having a:
 - Maximum area of 4m²; and
 - Not more than 2m wide elevation to the street; and
 - Not more than 3m in height.

- Private Amenity Space**
- Private amenity space, must be provided for the dwelling and is not less than 15m² with a minimum dimension of 3.0m and is directly accessible from a ground floor living area of the dwelling.

- Business Frontage**
- Business uses on-site must address the shared access easement over the adjoining commercial allotment 80001 (being the business frontage on the lot).
 - The business component may be either operated as Home Based Business with a maximum GFA for the business use of 50m², or as a business/shop use that can be leased independently of the residential use, in which case the business GFA may not exceed 90m² and the premises must comply with applicable requirements for fire separation.
 - The area shown on plan for the business use is indicative only and may adopt a different shape or extent (may extend further into the lot or extend over the ground and first floors) provided it addresses the business frontage of the lot directly.
 - Business must present a shop-front to the easement being:
 - significant glazing into the ground floor;
 - a clearly designated customer entry/shop door;
 - a small awning over the customer entry: 1.5m deep and min. 2m wide and 2.5m above the level of the footpath); AND
 - Signage on the face of the building or awning that is integrated into the design of the building and does not visually dominate.
 - Customer parking for the business on-site will be provided in the shared access easement and near to the shop-front at a rate of 1.5 parking spaces per tenancy.
 - Signage advertising the business is not permitted on the residential frontage of the allotment.
 - Service areas and bin storage areas must not be visible from the street or shared access easement. Where the business component is leased independently of the residential use the business/shop may either have its own area for bin storage or use a central storage and collection area shared with other tenancies and potentially located in the shared access easement over lot 80001.

Should the business have its own bin storage on site, this may be accessed via a pedestrian access way from the storage area out to the shared access easement for collection. Any on-site bin storage must be physically separated from the private amenity space of the residence to avoid any impact on the amenity of the dwelling/private amenity space.

- Privacy & Overlooking**
- Buildings must be sited and designed to provide adequate visual privacy for neighbours:
 - Where the distance separating a window or balcony of an adjoining dwelling from the side or rear boundary is less than 1.5m:
 - a permanent window and a balcony has a window/balcony screen extending across the line of sight from the sill to at least 1.5m above the adjacent floor level; or
 - a window has a sill height more than 1.5m above the adjacent floor level; or
 - a window has obscure glazing below 1.5m;where: Window and Window/Balcony Screen has the same meaning as in the Queensland Development Code.

- Fencing**
- Fencing along the residential street frontage must be either 50% transparent or max. 1.2m high, including fencing to secondary frontages (being to the shared access easement for lot 1 and to the shared driveway/pedestrian connection for lot 4). Fencing is not permitted to the business frontage of the lot.

- Residential Parking and Driveways**
- Residential garages are only permitted on the residential frontage of the lot.
 - The garage must be setback at least 1m behind the main residential facade, excluding balconies and porches, of the dwelling AND the garage doors must be articulated, comprise a mix of materials and colours, or are staggered.
 - The maximum width of a driveway at the lot boundary & where crossing the verge:
 - serving a double garage shall be 4.8m; and
 - serving a single garage shall be 3.0m.
 - Parking spaces on driveways do not have to comply with gradients in AS2890.
 - A maximum of one driveway per dwelling is permitted.
 - Driveways should avoid on-street works such as dedicated on-street parking bays, street trees, drainage pits and service pillars.
 - The minimum distance of a driveway from an intersection of one street with another street shall be 6.0 metres.

- Access Deeds**
- Access Deeds are required to be established on all dwellings / premises where there are adjoining built to boundary walls. These deeds will permit periodic maintenance access onto the roof of the dwelling on the adjoining lot, and permit roof water and waste to be deposited from time to time onto the roof.

- Rainwater Tanks**
- All dwellings must have a min 3000 litre rainwater tank. All tanks to residential dwellings must collect a minimum 50% roof area capture. All tanks must supply water to toilets, laundry, hot water and have a connection for external usage and must have a backup supply from the main potable water system .


- Definitions**
- Site Cover - the total area of the roof of the building (dwelling & business/shop premises combined) expressed as a percentage of the lot area, but which excludes eave overhangs .

Legend

- Maximum Building Envelope
- Indicative building footprint
- Minimum Building Setback Dimensions
- Recommended Built to Boundary Wall
- Optional Built to Boundary Wall
- Preferred private open space location 15m² min. with min. dimension of 3m
- Single, Tandem or Double Garage Location
- Indicative driveway location
- Shared access easement over commercial site 80001
- Indicative Location & Extent of Business Premises adjacent shared access easement (Shop or Business)
- Awning above business entry
- Preferred Location of Entry for Business Fronting Easement
- Preferred Letterbox Location for Business
- Preferred Location for Street Tree Planting
- Residential Dwelling Entry
- Preferred Residential Letterbox Location
- Possible Pedestrian Accessway to Bin Storage

Plan of Development Table	SOHO Allotments	
	Ground Floor	Upper Floors
Residential Frontage	2.4m	2.4m
Business Frontage - Built to Boundary	0.0m	0.0m
Business Frontage - Where not Built to Boundary	1.0m	1.0m
Garage	5.5m for single or tandem garages & 4.5m for double garages	n/a
Side - General Lots		
Built to Boundary	0.0m	0.0m
Non Built to Boundary *	0.9m	0.9m
Garage and On-site Car Parking		
On site parking requirements (minimum)	1 space to be covered and enclosed. Single garages (up to 4.5m in width) or tandem garages are acceptable. Double garages will not be permitted on a single storey dwelling on a lot less than 12.5m wide. Double garages may be permitted where the dwelling is more than one storey in height.	
Garage location	Garages are to be located along the built to boundary wall.	
Site Cover (maximum)	85%	

Note: * 2m Side setback on Lot 4 where shown on plan.




SOHO Allotment Diagram

Caloundra South - Precinct 2 Stockland


ANNEXURE 2

Siting and Fencing Examples






2 Car Option
1:200




Courtyard Option
1:200

Key

1. Gatehouse located adjacent to side boundary to maximise extent of useable courtyard with Northern aspect.
2. House front door located to side of house to maximise living area with Northern aspect.
3. Built to boundary garage wall to maximise amount of living area with Northern aspect
4. Locate Bin enclosure off driveway area for functionality and improve pedestrian visitor experience through gatehouse.
5. Extent of Glazing and doors from living area with Northern Aspect to be maximised. Configuration of doors should also consider functional pedestrian access for additional carapace.
6. Undercover outdoor living area provided with North Eastern aspect.
7. Northern courtyard landscaped in accordance with Stockland's Design Essential guidelines.
8. Separation between outdoor living area and visitor entry proposed via screening, change of level or landscaping.
9. Secondary car space provided in tandem arrangement proposed to be multipurpose through considerate design of pavement and pergola structure. Stencilled concrete, pavers, or exposed aggregate pavement is recommended. It is noted that plain concrete to the secondary car space will not be approved.
10. To maximise opportunity for dual use of carapace, an automated gate configured to not swing over the road verge or compromise use of multi purpose space is recommended.
11. Landscape structure/Pergola proposed over secondary car space to soften appearance from street. Solid roof integrated with roof design of residence with a 2.5m setback may also be considered.
12. Street fencing designed in accordance with Stockland's Design Essential guidelines




Pool Option
1:200





Courtyard Option
1:200

Key

1. Gatehouse located adjacent to side boundary to maximise extent of useable courtyard with Northern aspect.
2. House front door located to side of house to maximise living area with Northern aspect.
3. Built to boundary garage wall to maximise amount of living area with Northern aspect
4. Locate Bin enclosure off driveway area for functionality and improve pedestrian visitor experience through gatehouse.
5. Extent of Glazing and doors from living area with Northern Aspect to be maximised. Configuration of doors should also consider functional pedestrian access for additional carapace.
6. Undercover outdoor living area provided with North Eastern aspect.
7. Northern courtyard landscaped in accordance with Stockland's Design Essential guidelines.
8. Separation between outdoor living area and visitor entry proposed via screening, change of level or landscaping.
9. Secondary car space provided in tandem arrangement recommended to maximise size of Northern aspect courtyard. It is noted that plain concrete to this area will not be approved.
10. Landscape structure/Pergola proposed over secondary car space to soften appearance from street. Solid roof integrated with roof design of residence with a 2.5m setback may also be considered.
11. Street fencing designed in accordance with Stockland's Design Essential guidelines
12. Introduction of additional articulation to the Eastern elevation is recommended to allow rooms to the rear of the residence to achieve a Northern aspect.
13. Double car garage
14. Gated Secondary access between private Northern courtyard and driveway recommended.




Pool Option
1:200





Courtyard Option
1:200

Key

1. Gatehouse located adjacent to side boundary to maximise extent of useable courtyard with Northern aspect.
2. House front door located to side of house to maximise living area with Northern aspect.
3. Built to boundary garage wall to maximise amount of living area with Northern aspect
4. Locate Bin enclosure off driveway area for functionality and improve pedestrian visitor experience through gatehouse.
5. Extent of Glazing and doors from living area with Northern Aspect to be maximised. Configuration of doors should also consider functional pedestrian access for additional carapace.
6. Undercover outdoor living area provided with North Eastern aspect.
7. Northern courtyard landscaped in accordance with Stockland's Design Essential guidelines.
8. Separation between outdoor living area and visitor entry proposed via screening, change of level or landscaping.
9. Double car garage
10. Gated Secondary access between private Northern courtyard and driveway recommended.
11. Street fencing designed in accordance with Stockland's Design Essential guidelines
12. Introduction of additional articulation to the Eastern elevation is recommended to allow rooms to the rear of the residence to achieve a Northern aspect.
13. Where entry is located within the Northern elevation of the residence. it is recommended that the width does not exceed 1.5 so not to adversely compromise the extent of living area with a Northern aspect.



Pool Option
1:200



Courtyard Option
1:200

Key

1. Entry is located within the Northern elevation of the residence. it is recommended that the width does not exceed 1.5 so not to adversely compromise the extent of living area with a Northern aspect.
2. Locate Bin enclosure off driveway area for functionality and improve pedestrian visitor experience through gatehouse.
3. Built to boundary garage wall to maximise amount of living area with Northern aspect
4. Double car garage
5. Extent of Glazing and doors from living area with Northern Aspect to be maximised where an appropriate overhang is provided.
6. Undercover outdoor living area provided with North Eastern aspect.
7. Northern courtyard landscaped in accordance with Stockland's Design Essential guidelines.
8. Separation between outdoor living area and visitor entry proposed via screening, change of level or landscaping.
9. Street fencing designed in accordance with Stockland's Design Essential guidelines
10. Introduction of additional articulation to the Eastern elevation is recommended to allow rooms to the rear of the residence to achieve a Northern aspect.

Fence Design | Vertical Panels

"Vertical" fencing panels are typically the preferred choice within developing housing areas, given the levels of security provided and their economy. This fencing typology can be enhanced through the use of contrasting materials and colours, but more importantly through the use of landscaping positioned on either side of the fence, considerably improving the privacy qualities achieved. The introduction of members "on edge" provide an inherent level of privacy from the approaching oblique angles whilst providing excellent surveillance from within.



Fence Design | Horizontal Panels

"Horizontal" fencing elements maximise the visual transparency available through street fencing, though no protection against the oblique view lines. Where privacy is a concern, the introduction of landscape elements to either side of the fence is recommended to diffuse these sight lines. Consideration to detailing is recommended, particularly in regards to configuration of dado panels and horizontal screen supports.



Fence Design | Pattern Arrangement

Pattern Arrangement systems typically combine areas of privacy to private courtyards with areas of good visual transparency to and from the private realm. Consideration of the position of the solid elements relative to the respective functional purpose and utilitarian nature of the courtyards should be given. This varying level of transparency is often achieved through the "patterning" of the same material, but can include the use of contrasting materials for particular aesthetic affect. The resultant affect is not only positive on the streets cape, but also provides good levels of privacy to the courtyard users.



Fence Design | Feature Panels

"Feature Panel" fencing provides high levels of privacy through the utilisation of depth of view techniques. The provision of a pattern (and often artistic element) along the street edge provides the passer by an object to focus on without taking in the activities beyond. For the "static occupant", these screens serve as a diffuser of light and view, but are still transparent enough to allow good surveillance of the public realm.



ANNEXURE 3

Landscape requirements	
-----------------------------------	--

Contents

Trees & Palms Schedule - Native	3
Trees & Palms - Native	4
Shrubs Schedule - Native	6
Shrubs - Native	7
Shrubs Schedule - Exotic	10
Shrubs - Exotic	11
Groundcovers & Grasses Schedule - Native	12
Groundcovers & Grasses - Native	13
Groundcovers & Grasses Schedule - Exotic	15
Groundcovers & Grasses - Exotic	16

Trees & Palms Schedule

NATIVE

NO.	BOTANICAL NAME	COMMON NAME	HEIGHT	SPREAD	SHAPE	COLOUR	SEASON	EVERGREEN/ DECIDUOUS	BUSH TUCKER/ EDIBLE	COMMENTS
01	<i>Acmena smithii</i>	Narrow-leafed Lillypilly	8m	4m			Spring - Autumn	Evergreen	✓ fruit	
02	<i>Archontophoenix cunninghamiana</i>	Bangalow Palm	15m	4m			Summer	Evergreen	✗	Mass plant in various heights, minimum 3 plants per clump
03	<i>Backhousia citrifodora</i>	Lemon Myrtle	4-6m	3-5m			Summer-Autumn	Evergreen	✗	Scented leaves, good for a sensory garden
04	<i>Backhousia myrtifolia</i>	Carrol	4m	3m			Spring	Evergreen	✗	Good background screen
05	<i>Banksia aemula</i>	Wallum Banksia	5m	5m			Autumn-Winter	Evergreen	✓ nectar	Distinctive form Bird attracting
06	<i>Banksia integrifolia</i>	Coastal Banksia	7m	5m			Summer-Winter	Evergreen	✓ nectar	Bird attracting
07	<i>Buckinghamia celsissima</i>	Ivory Curl Tree	6-8m	3-5m			Summer	Evergreen	✗	Floral display
08	<i>Callistemon salignus</i>	Pink Tips Bottlebrush	6m	4m			Spring	Evergreen	✓ nectar	Damp areas
09	<i>Cupaniopsis anacardioides</i>	Beach Tamarind	8-10m	5-8m			Spring	Evergreen	✗	
10	<i>Elaeocarpus reticulatus</i>	Blue Berry Ash	8-25m	3-5m			Summer	Evergreen	✗	
11	<i>Harpullia pendula</i>	Tulipwood	8m	6m			Summer-Autumn	Evergreen	✗	
12	<i>Livistona australis</i>	Cabbage Palm	15m	5m			Summer	Evergreen	✓	Grouped plantings
13	<i>Pandanus tectorius</i>	Screw Pine	8m	6m			Spring-Summer	Evergreen	✗	
14	<i>Pandanus utilis</i>	Pandanus - Red Edge	9m	6m			Spring-Summer	Evergreen	✗	
15	<i>Randia fitzalanii</i>	Native Gardenia	6m	6m			Spring	Evergreen	✓ fruit	Scented Flowers, edible fruit
16	<i>Rhapis excelsa</i>	Broad Leaved Lady Palm	2m	3m			Spring	Evergreen	✗	Part Shade
17	<i>Strelitzia nicolii</i>	Giant White Bird Strelizia	6m	2m			Spring-Summer	Evergreen	✗	Full sun, part shade, can be hedged (used as shrub)
18	<i>Syzygium sp</i>	Lilly Pilly	10m	5m			Spring	Evergreen	✓	
19	<i>Tristaniopsis laurina 'luscious'</i>	Water Gum	6-8m	4-6m			Summer	Evergreen	✗	Damp areas
20	<i>Viburnum odoratissimum</i>	Sweet Viburnum	4m	3m			Spring - Summer	Evergreen	✗	Full sun, part shade, can be hedged (used as shrub)
21	<i>Xanthostemon chrysanthus</i>	Golden Penda	10-15m	6-12m			Spring	Evergreen	✗	Medium shade tree in open spaces

Trees & Palms

NATIVE



01 *Acmena smithii*



02 *Archontophoenix cunninghamina*




03 *Backhousia citriodora*



04 *Backhousia myrtifolia*



05 *Banksia aemula*



06 *Banksia integrifolia*



07 *Buckinghamia celsissima*



08 *Callistemon salignus*



09 *Cupaniopsis anacardioides*



10 *Elaeocarpus reticulatus*



11 *Harpullia pendula*



12 *Livistona australis*

Trees & Palms

NATIVE



13 *Pandanus tectorius*



14 *Pandanus utilis*



15 *Randia fitzalanii*



16 *Rhapis excelsa*



17 *Strelitzia reginae*



18 *Syzygium* sp.



19 *Tristania laurina* 'luscious'



















































































20 *Viburnum odoratissimum*



21 *Xanthostemon chrysanthus*

Shrubs Schedule

NATIVE

NO.	BOTANICAL NAME	COMMON NAME	HEIGHT	SPREAD	SHAPE	COLOUR	SEASON	EVERGREEN/ DECIDUOUS	FEATURES	FRONT ENTRIES	GENERAL PLANTING	BUSH TUCKER/ EDIBLE	COMMENTS
01	<i>Acmena Smithii</i> 'Allyn Magic'	Dwarf Lillypilly	0.5 m	0.5 m		 	Spring	Evergreen	✓	✓	✗	✗	Low hedging plant
02	<i>Alpinea caerulea</i>	Native Ginger	2 - 2.5m	1 - 2 m			Autumn-Winter	Evergreen	✓	✓	✓	✓fruit	Shady position
03	<i>Alpinea zerumbet</i> 'variegata'	Variegated Ginger	1.5 - 2.4 m	1.2 - 1.8 m		 	Spring-Summer	Evergreen	✓	✓	✓	✓fruit	Shady position
04	<i>Banksia oblongifolia</i>	Fern-leafed Banksia	1.5-3 m	1.5 m			Summer	Evergreen	✓	✓	✓	✓fruit	Shady position
05	<i>Banksia robur</i>	Swamp Banksia	2-3 m	2-3 m		 	Spring-Summer	Evergreen	✓	✓	✓	✓nectar	Bird attracting
06	<i>Banksia spinulosa</i>	Hairpin Banksia	1-3 m	2 m		 	Winter-Spring	Evergreen	✓	✓	✓	✓nectar	Bird attracting
07	<i>Callistemon 'Captain Cook'</i>	Bottlebrush	1.5 m	1.5 m		 	Autumn-Spring	Evergreen	✓	✓	✓	✓nectar	Bird attracting
08	<i>Callistemon 'Little John'</i>	Bottlebrush	0.6 m	0.6 m		 	Spring	Evergreen	✓	✓	✓	✓nectar	Bird attracting
09	<i>Callistemon 'Wilderness White'</i>	Bottlebrush	3 m	1.6 m		 	Summer	Evergreen	✓	✓	✓	✓nectar	Bird attracting
10	<i>Callistemon polandii</i>	Gold Tipped Bottlebrush	4 m	3 m		 	Spring	Evergreen	✓	✓	✓	✓nectar	Bird attracting
11	<i>Cordyline stricta</i>	Slender Palm Lily	5 m	1.5 m			Summer	Evergreen	✓	✓	✗	✗	Shade/part shade
12	<i>Cordyline rubra</i>	Red Palm Lily	2-3 m	1-2 m		 	Spring	Evergreen	✓	✓	✗	✗	Shade/part shade
13	<i>Cordyline australis</i> 'Red Sensation'	Palm Lily	3-9 m	0.9-4.6m			Late Spring	Evergreen	✓	✓	✗	✗	Shade/part shade Coloured foliage
14	<i>Grevillea 'Honey Gem'</i>	Honey Gem	4 m	3 m		 	Winter-Spring	Evergreen	✓	✓	✓	✓nectar	Bird attracting
15	<i>Grevillea 'Moonlight'</i>	Moonlight	5 m	3 m		 	Year Round	Evergreen	✓	✓	✓	✓nectar	Bird attracting
16	<i>Grevillea 'Misty Pink'</i>	Misty Pink	3 m	2.5-3 m		 	Winter-Spring- Summer	Evergreen	✓	✓	✓	✓nectar	Bird attracting
17	<i>Grevillea 'Orange Marmalade'</i>	Orange Marmalade	2.5 m	2 m		 	Year Round	Evergreen	✓	✓	✓	✓nectar	Bird attracting
18	<i>Leptospermum petersonii</i>	Lemon Scented Tea Tree	1.5-2 m	1.5 m		 	Spring	Evergreen	✓	✓	✓	✗	Mass planting
19	<i>Melaleuca 'Claret Tops'</i>	Honey Myrtle	1-1.2 m	0.6-0.8 m		 	Spring	Evergreen	✓	✓	✓	✗	Prunes well
20	<i>Melaleuca 'Snowflake'</i>	Manuka	1.8-2.4 m	2.4-3 m		 	Year Round	Evergreen	✓	✓	✓	✗	Prunes well
21	<i>Syzygium 'Cascade'</i>	Weeping Lillypilly	2-3 m	1.5 m		 	Summer	Evergreen	✓	✓	✓	✓fruit	Medium hedge
22	<i>Syzygium australe</i> 'Aussie Southern'	Aussie Southern Lillypilly	2-3 m	3-5 m		 	Spring-Summer	Evergreen	✓	✓	✓	✓fruit	Medium hedge
23	<i>Syzygium australe</i> 'Elite'	Elite Lillypilly	3-5 m	2-3 m		 	Spring-Summer	Evergreen	✓	✓	✓	✓fruit	Medium hedge
24	<i>Syzygium paniculatum</i>	Magenta Cherry	5-8 m	4-8 m		 	Summer	Evergreen	✓	✓	✓	✓fruit	Medium hedge
25	<i>Westringia fruticosa</i>	Coastal Rosemary	2 m	5 m		 	Year Round	Evergreen	✓	✓	✓	✗	Low Hedge
26	<i>Westringia 'Xena'</i>	Coastal Rosemary	1 m	1 m		 	Year Round	Evergreen	✓	✓	✓	✗	Low Hedge
27	<i>Xanthorrhoea species</i>	Grass Tree	Up to 2 m	1.6 m		 	Spring	Evergreen	✓	✓	✓	✓nectar	Feature Plant
28	<i>Xanthostemon 'Little Penda'</i>	Dwarf Xanthostemon	Up to 5 m	4-6m		 	Spring	Evergreen	✓	✓	✓	✓nectar	Slow growing

Shrubs

NATIVE



01 *Acmena Smithii* 'Allyn Magic'




02 *Alpinea caerulea*



03 *Alpinea zerumbet* 'variegata'



04 *Banksia oblongifolia*



05 *Banksia robur*



06 *Banksia spinulosa*



07 *Callistemon* 'Captain Cook'



08 *Callistemon* 'Little John'



09 *Callistemon* 'Wilderness White'



10 *Callistemon polandii*



11 *Cordyline stricta*



12 *Cordyline rubra*

Shrubs

NATIVE



13 *Cordyline australis* 'Red Sensation'



14 *Grevillea* 'Honey Gem'




15 *Grevillea* 'Moonlight'



16 *Grevillea* 'Misty Pink'



17 *Grevillea* 'Orange Marmalade'



18 *Leptospermum petersonii*




19 *Melaleuca* 'Claret Tops'



20 *Melaleuca* 'Snowflake'



21 *Syzygium* 'Cascade'



22 *Syzygium australe* 'Aussie Southern'



23 *Syzygium australe* 'Elite'



24 *Syzygium paniculatum*

Shrubs

NATIVE



25 *Westringia fruticosa*



26 *Westringia 'Xena'*





27 *Xanthorrhoea* species



28 *Xanthostemon 'Little Penda'*

Shrubs Schedule

EXOTIC

NO.	BOTANICAL NAME	COMMON NAME	HEIGHT	SPREAD	SHAPE	COLOUR	SEASON	EVERGREEN/ DECIDUOUS	FEATURES	FRONT ENTRIES	GENERAL PLANTING	BUSH TUCKER/ EDIBLE	COMMENTS
01	<i>Acalypha 'Inferno'</i>	Acalypha	2 m	1 m		 	Spring	Evergreen	✓	✓	✗	✗	Red/bronze foliage
02	<i>Acalypha wilkesiana 'Macrophylla'</i>	Red / Copper Leaf	3 m	2 m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	Coloured foliage
03	<i>Heliconia 'Red Xmas'</i>	Red Christmas	1 m	1.2m		 	Winter-Spring	Evergreen	✓	✓	✓	✗	Shady position
04	<i>Heliconia 'Scarlet Torch'</i>	Torch Heliconia	1.5-1.8 m	1.5-2 m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	Shady position
05	<i>Hibiscus rosa-sinensis</i>	Rose of China	2.5-5 m	1.5-3 m		 	Summer-Autumn	Evergreen	✓	✓	✓	✗	Large flowers
06	<i>Ixora 'Prince of Orange'</i>	Prince of Orange	2 m	1.5 m		 	Spring-Autumn	Evergreen	✓	✓	✓	✗	Part shade
07	<i>Ixora 'Pink Malay'</i>	Pink Malay	1 m	1 m		 	Spring	Evergreen	✓	✓	✓	✗	Part shade
08	<i>Metrosideros 'Fiji Fire'</i>	Fiji Christmas Bush	3 m	1 m		 	Summer	Evergreen	✓	✓	✓	✗	Screening shrub
09	<i>Metrosideros thomasi</i>	NZ Christmas Bush	5 m	5 m		 	Summer	Evergreen	✓	✓	✓	✗	Screening shrub
10	<i>Russelia equisetiformis</i>	Firecracker Plant	5 m	1.5 m		 	Year Round	Evergreen	✓	✓	✓	✗	Colourful flowers
11	<i>Strelitzia reginae</i>	Bird of Paradise	2-3 m	1-2 m		 	Winter-Spring	Evergreen	✓	✓	✓	✗	Feature plant
12	<i>Zamia furfuracea</i>	Cardboard Palm	0.6-1.5 m	1.5-2.5m		 	Late Spring	Evergreen	✓	✓	✓	✗	Feature Plant

Shrubs

EXOTIC



01 *Acalypha* 'Inferno'



02 *Acalypha wilkesiana* 'Macrophylla'



03 *Heliconia* 'Red Xmas'



04 *Heliconia* 'Scarlet Torch'



05 *Hibiscus rosa-sinensis*




06 *Ixora* 'Prince of Orange'



07 *Ixora* 'Pink Malay'



08 *Metrosideros* 'Fiji Fire'



09 *Metrosideros thomasi*



10 *Russelia equisetiformis*













































11 *Strelitzia reginae*



12 *Zamia furfuracea*

Groundcovers & Grasses Schedule

NATIVE

NO.	BOTANICAL NAME	COMMON NAME	HEIGHT	SPREAD	SHAPE	COLOUR	SEASON	EVERGREEN/ DECIDUOUS	FEATURES	FRONT ENTRIES	GENERAL PLANTING	BUSH TUCKER/ EDIBLE	COMMENTS
01	<i>Anigozanthus 'big red'</i>	Red Kangaroo Paw	0-2m	up to 1m			Spring-Summer	Evergreen	✓	✓	✓	✗	Full sun
02	<i>Anigozanthus 'yellow gem'</i>	Yellow Kangaroos Paw	0-2m	up to 1m			Spring-Summer	Evergreen	✓	✓	✓	✗	Full sun
03	<i>Asplenium australasicum</i>	Crows Nest Fern	0.5m-1.5m	up to 2m			Year round	Evergreen	✓	✓	✓	✗	Shade
04	<i>Babingtonia virgata 'la petite'</i>	Dwarf Baeckea	0.5m-1m	0.5m-1.5m			Summer	Evergreen	✓	✓	✓	✗	
05	<i>Blechnum cartilagineum</i>	Gristle Fern	0.5m-1.5m	0.5m-1.5m			Year round	Evergreen	✓	✓	✓	✗	Shade
06	<i>Cissus antarctica</i>	Native Grape	1m-5m	up to 1.5m			Spring	Evergreen	✓	✓	✓	✓ fruit	Sun / part shade
07	<i>Cissus hypoglauca</i>	Water Vine	1m-1.5m	up to 1.5m			Spring-Summer	Evergreen	✓	✓	✓	✓ fruit	Shade
08	<i>Crinum pedunculatum</i>	Swamp Lily	1m-2m	up to 1m			Spring-Summer	Evergreen	✓	✓	✓	✗	
09	<i>Dianella brevipedunculata</i>	Blue Flax Lily	0.5m-1m	up to 1.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
10	<i>Dianella caerulea</i>	Flax Lily	0.5m-1m	up to 2.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
11	<i>Dianella congesta</i>	Flax Lily	0.5m-1m	up to 1.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
12	<i>Dianella revoluta</i>	Flax Lily	0.5m-1m	up to 1.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
13	<i>Ficinia nodosa</i>	Knobbly Club Rush	0.5m-3m	up to 2.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
14	<i>Grevillea 'royal mantle'</i>	Royal Mantle	1m-2m	up to 3m			Winter-Spring	Evergreen	✓	✓	✓	✗	raised planters tops of walls
15	<i>Hibbertia scandens</i>	Snake Vine	0.5m-3m	1m-5m			Spring-Summer	Evergreen	✓	✓	✓	✗	
16	<i>Lomandra hystrix</i>	Slender Mat Rush	0.5m-1m	1m-1.5m			Spring-Summer	Evergreen	✓	✓	✓	✓	More moisture than L. longifolia, leaf bases
17	<i>Lomandra longifolia</i>	Mat Rush	0.5m-1m	1m-1.5m			Spring-Summer	Evergreen	✓	✓	✓	✓	Less moisture than L. hystrix, leaf bases
18	<i>Melaleuca thymifolia</i>	Dwarf Honey Myrtle	1m-1.5m	1m-2m			Winter-Summer	Evergreen	✓	✓	✓	✗	
19	<i>Myoporum ellipticum</i>	Coastal Myoporum	0.5m-1m	up to 2m			Summer-Autumn	Evergreen	✓	✓	✓	✗	
20	<i>Rhoeo species</i>	Moses in a Cradle	0.5m	0.5m			Summer	Evergreen	✓	✓	✓	✗	Feature plant red / purple colour
21	<i>Scaevola'purple fanfare'</i>	Fan Flower	0.5m	up to 1.5m			Spring-Summer	Evergreen	✓	✓	✓	✗	Tops of walls rockeries
22	<i>Viola hederacea</i>	Native Violet	0.5m-1m	0.5m-1m			Year round	Evergreen	✓	✓	✓	✗	Shade spreads under plantings
23	<i>Vitex ovata</i>	Prostrate Vitex	0.5m	up to 2m			Summer	Evergreen	✓	✓	✓	✗	Full sun low cover for exposed areas

Groundcovers & Grasses

NATIVE



01 *Anigozanthus* 'big red'



02 *Anigozanthus* 'yellow gem'



03 *Asplenium australasicum*



04 *Babingtonia virgata* 'la petite'



05 *Blechnum cartilagineum*




06 *Cissus antarctica*



07 *Cissus hypoglauca*



08 *Crinum pedunculatum*



09 *Dianella brevipedunculata*



10 *Dianella caerulea*



11 *Dianella congesta*



12 *Dianella revoluta*

Groundcovers & Grasses

NATIVE



13 *Ficinia nodosa*



14 *Grevillea 'royal mantle'*



15 *Hibbertia scandens*



16 *Lomandra hystrix*



17 *Lomandra longifolia*



18 *Melaleuca thymifolia*



19 *Myoporum ellipticum*



20 *Rhoeo species*



21 *Scaevola "purple fanfare"*




















































22 *Viola hederacea*



23 *Vitex ovata*

Groundcovers & Grasses Schedule

EXOTIC

NO.	BOTANICAL NAME	COMMON NAME	HEIGHT	SPREAD	SHAPE	COLOUR	SEASON	EVERGREEN/ DECIDUOUS	FEATURES	FRONT ENTRIES	GENERAL PLANTING	BUSH TUCKER/ EDIBLE	COMMENTS
01	<i>Agapanthus africanus</i>	Agapanthus	0.5m-1m	up to 1.5m		 	Summer	Evergreen	✓	✓	✓	✗	
02	<i>Dietes bicolor</i>	Yellow Wild Iris	0.5m-1m	0.5m-1m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
03	<i>Dietes grandiflora</i>	Wild Iris	0.5m-1m	0.5m-1m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
04	<i>Ergeron karvinskiansis</i>	Seaside Daisy	15cm-25cm	up to 20cm		 	Winter-Spring	Evergreen	✓	✓	✓	✗	
05	<i>Evolvulus pilosus</i>	Blue Eyes	30cm	up to 1m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
06	<i>Formium species</i>	NZ Flax	1m-4m	up to 2m		 	Spring	Evergreen	✓	✓	✓	✗	Architectural Plant
07	<i>Hemerocallis hybrids</i>	Day Lillies	0.5m-1m	up to 1m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
08	<i>Hymenocallis littoralis</i>	Spider Lily	0.5m-1m	up to 1m		 	Summer	Evergreen	✓	✓	✓	✗	
09	<i>Juniperus conferta</i>	Shore Juniper	0-0.5m	3m-5m		 	Spring	Evergreen	✓	✓	✓	✗	
10	<i>Liriope 'Evergreen Giant'</i>	Evergreen Giant	0.5m-1m	0.5m-1m		 	Summer-Autumn	Evergreen	✓	✓	✓	✗	
11	<i>Liriope muscari</i>	Lilyturf	0.5m-1m	0.5m-1m		 	Spring	Evergreen	✓	✓	✓	✗	
12	<i>Nandina domestica</i> <i>Pygmaea 'Nana'</i>	Dwarf Sacred Bamboo	0.5m	0.5m-1m		 	Summer-Winter	Evergreen	✓	✓	✓	✗	
13	<i>Ophiopogon japonicus</i>	Mondo Grass	15cm-30cm	10cm-20cm		 	Summer	Evergreen	✓	✓	✓	✗	
14	<i>Ophiopogon 'Stripey White'</i>	Variegated Lily	0-0.5m	up to 0.5m		 	Spring	Evergreen	✓	✓	✓	✗	Syn. Liriope Stripey White
15	<i>Trachelospermum "Tricolour"</i>	Variegated Jasmine	0.5m-2m	up to 1.5m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
16	<i>Trachelospermum asiaticum</i>	Yellow Star Jasmine	6m-9m	up to 4m		 	Spring-Summer	Evergreen	✓	✓	✓	✗	
17	<i>Tulbaghia violacea</i>	Society Garlic	0.5m	0-0.5m			Spring-Autumn	Evergreen	✓	✓	✓	✗	

Groundcovers & Grasses

EXOTIC



01 *Agapanthus africanus*



02 *Dietes bicolor*



03 *Dietes grandiflora*



04 *Ergeron karvinskiansis*



05 *Evolvulus pilosus*



06 *Formium species*



07 *Hemerocallis hybrids*



08 *Hymenocallis littoralis*



09 *Juniperus conferta*



10 *Liriope "Evergreen Giant"*



11 *Liriope muscari*



12 *Nandina domestica Pygmaea 'Nana'*

Groundcovers & Grasses

EXOTIC



13 *Ophiopogon japonicus*



14 *Ophiopogon* 'Stripey White'



15 *Trachelospermum* "Tricolour"



16 *Trachelospermum asiaticum*



17 *Tulbaghia violacea*