



altrove

*The Park Front  
Design Guidelines*



## Approval Process

Stockland has prepared these Design Guidelines to guide house design at Altrove.

The Design Guidelines should be read in conjunction with the NSW Housing Code, which applies for this development site. You may be able to seek a Complying Development Certificate for your proposed home.

You should talk to your builder/designer about this option, which may save you time and money. Alternatively, you may wish to seek guidance from the relevant Council authority bodies and submit

a development application to Council. To ensure a smooth design review process, please pass this document on to your designer/builder so that a 'Home Design Package' can be prepared for endorsement by Stockland. This Package must include

a Site Plan (1:200); Floor Plans, Elevations, Sections (1:100); External colours and materials selection; Landscape Plan (can be shown on the site plan), or submitted separately.

The key steps in the Approval process are outlined in the following chart (below).



## 1.0 Presenting your home to the street

### Park Front Lots

Please refer to the map included at the back of the Design Guidelines to determine which *park front lots* must be built as double storey homes and which *park front lots* must be built as single storey dwellings.

### Home style

Your home design must be 'contemporary'. This means that house designs that mimic a historic style will not be permitted. Historic elements used on a design, such as quoins, keystones, corbelling, fretwork or lacework will not be permitted.

### Entry features

The design of the home must incorporate either a porch, portico or verandah that is:

- Pretruding 1M in front of the building line.
- Adequately covered, clearly defined and visible from the street.


Refer to illustration 1

### Entrance visibility

To enhance the architectural style of the homes, the front entry door must be seen from the street and is encouraged to be a feature style door.

### 1. Entry feature/articulation

1a: Entry feature/articulation



## 2.0 Roofs

### Roof pitch

- Hipped and Gable roofs must have a minimum roof pitch of 25 degrees. Other roof types such as skillion roofs is encouraged.

### Roof material

- The roof are to be constructed of either sheet metal or tiles in a matte finish.
- Roof can be skillion, hipped and gable. Curved or butterfly roofs are not permitted.

### Roof colour

- Roof tile colours are to be selected from the pre-endorsed list attached at the back of the design guideline.

### Eaves

- Eaves, excluding fascia and gutter, are to be provided to all habitable rooms and must overhang by a minimum of 450mm. Where zero-lot boundaries apply, the non-habitable rooms (ie Garages) are exempt from this requirement.
- Where the design is contemporary and does not allow for any eaves, the use of awnings and/or sun shade materials is strongly encouraged where there is a window to improve energy efficiency.



## 3.0 Building Materials

### Mix of materials

- The primary base material type for the front of the dwelling is to be a masonry material (face brick).
- For single storey homes a minimum of one additional material type must be incorporated into the front facade in another colour or tone variations that is complementary to the main facade material.
- For double storey homes a minimum of two additional material types in at least two different colour or tone variations that are complementary to the main facade material are to be incorporated.
- Additional material types to be incorporated include timber, feature stonework, weatherboard, fibre-cement sheeting, marine grade plywood or other architectural style claddings.







#### External colour selection

- The colours of the main material on the front facade are to be of natural, earthy and neutral tones. Red or black tones are not permitted.



- Brickworks with red or black tones will not be considered as the main material of the home.
- Accent material colours should complement the main material, and be used to express individuality for the home. In these architectural elements, stronger colours can be used to highlight architectural features.
- Gutter colours should match the colour of the roof material, to emphasise the roof and eaves as a consistent element.
- Downpipes or vertical guttering should not be highlighted and should be coloured to blend into the adjacent wall colour.

## 4.0 Corner Lots

### Wrapping the corner

Houses on corner lots must have some form of articulation that addresses both streets and that is visible to the public. The articulation should be incorporated on the primary facade and should wrap around the corner to also be incorporated on the secondary facade. Examples of these could be as follows;

- Recessing or projecting architectural elements that are substantial enough to articulate the corner;
- Windows that address both streets.

### Secondary street treatment

- Blank walls are not permitted on the secondary street, and the secondary street wall must also be articulated. Windows should be incorporated on the secondary facade, and they should be of similar material, profile, finish and colour as those used on the primary facade.
- On the side wall that faces the secondary street no straight section of the wall should be longer than 12m. A step of at least 900mm should be incorporated to break up these sections and to provide interest to the facade along the secondary street.





## 5.0 Garages

### Garage widths

- Garages are to be setback a minimum of 1m from the main building line of the house, to ensure that they minimise scale and that they are not a dominant feature of the home.
- Triple Garages are not permitted.
- Car ports are not permitted.

### Garage colour and material

- The Garage Door is to be either Panel Lift, Panel Glide, or Tilt-A-Door style. Roller Door garages are not permitted.
- The garage is to be constructed in the same materials and style as the house, to add to and complement the overall design of the home.

## 6.0 Driveways and crossovers

### Driveway colour and material

- Between the kerb and the property boundary the driveway is to be of a consistent width (tapered or splayed crossovers are not permitted).
- The maximum width for the driveway crossover is 4m.
  - Driveways are to be offset at least 500mm from nearest side boundary. Shrubs and/or other plants are to be provided to screen the gap in between the driveway side boundary.
  - Driveways are to be constructed of a single-colour concrete or paver. The colour of the driveway must be a grey tone, and must be shown on the dwelling and/or landscape drawings. Stencilled driveways are not permitted.
  - Refer to Blacktown City Council's invert and crossover details for crossover requirements.

## 7.0 Landscaping

Each lot is to provide:


- a feature tree with a minimum pot size of 75L planted in the front setback of the house.
- a garden bed along the front setback. Minimum 400mm deep with 300mm pot size hedges planted every 300mm at a maximum spacing. This could be located along the front boundary or elsewhere within the front setback.
- It is recommended that a defined footpath is to be provided as a walkway from the front boundary to the entrance of the home.

*Refer to illustration 2*





## 2. Front Landscaping (Guide Only)





## 8.0 Fencing and Retaining Walls

### Side and rear fencing

- Side and rear boundary fencing must be 1.8m high sheet metal in COLORBOND™ steel - Grey Ridge. Side boundary fencing must be setback at least 2m behind the front main building line.
- Side gates may be provided for security, gates can be aluminium steel battens with 20mm gap or a solid COLORBOND™ gate in the colour Grey Ridge.
- Where the fencing is constructed on top of the retaining wall, the height of the fence must be the same as a normal ground level fence i.e. 1.8m high.

### Corner lot side fencing (secondary street frontage)

- A 150mm wide planting strip is to be planted to the front of the fence.
- Secondary fencing for the corner lots must be 1.8m high constructed of masonry piers with (face brick or painted render to complement the dwelling colours) in between every second panel infill of either:
  - COLORBOND™ fencing (Lysaght Spanscreen™ or Smartscreen™) in Grey Ridge or
  - COLORBOND™ batten infill panels in Grey Ridge.
- The secondary street side boundary fencing must be setback at least 4m behind the main building line or behind the secondary facade articulation.

## 9.0 Exteriors

### Outbuildings

- The appearance of any outbuildings should be carefully designed:
  - if less than 10sqm they must be constructed in an approved finish to complement the house;
  - if greater than 10sqm they must be constructed so that the external appearance matches the main house in colours, materials and style.


### Screening

Ground-mounted equipment must be screened from public view and must not be visible from any street or public reserve. This includes, but is not limited to: heating and cooling units, rubbish disposal containers, swimming pools, boats, caravans, rain water tanks and clothes hoists.

- Non-ground mounted equipment must be located to minimise its visual impact on the street. They generally should not be visible from the street or any public reserve. This includes, but is not limited to: satellite dishes, TV aerials, external hot water services, water tanks, air-conditioning units, heating units, spa pumps, outbuildings etc.

### Letter Boxes

- Must be constructed out of rendered or masonry materials in a colour or tone that complements the colour of the driveway and/or house.
- The street number on the letterbox should be large enough to be visible from the street and complement the overall design intent of the home.
- A letter box must be provided to your home prior to occupation.











**Legend**

- Park Front Design Guidelines Apply  
(Single Storey only permitted)
- Park Front Design Guidelines Apply  
(Double Storey only permitted)



# Endorsed Roof Tile

## Bristle Roofing

<b>Concrete Tiles</b>	<b>Classic Shingle</b>	Bark
		Coal
		Gunmetal
		Mica
		Savannah
		Pebble
	<b>Prestige Smooth</b>	Mercury
		Palladium
		Titanium
		Tungsten

## Boral Roof Tiles

<b>Terracotta Tiles</b>	<b>Shingle</b>	Mineral
		Savanna
		Antique Bronze
		Asphalt
		Scoria
		Ghost Gum Grey
		Wild Choc
<b>Concrete Tiles</b>	<b>Vogue</b>	Shale
		Gunmetal
		Twilight
		Charcoal Grey
		Stonewall
		Taupe
	<b>Linea</b>	Charcoal Grey

## Monier

<b>Terracotta Tiles</b>	<b>Nullarbor</b>	Granite
		Slate Grey
<b>Concrete Tiles</b>	<b>Horizon/Traditional</b>	Barramundi
		Camelot
		Babylon
		Silver Perch
		Atlantis
		Wollemi
		Aniseed
		Caraway
		Fig



**Stockland**  
*it's your place*



### ***Design Variation:***

Where designs are proposed that vary from these Design Guidelines they will be assessed on their design merit by the Design Review Panel. Variations will only be considered where it can be demonstrated that they still achieve the desired objectives for the creation of an aspirational community in Altrove.

### ***House Design and Landscape Plan:***

Stockland will accept and approve separately, home design and landscape plans if required. Owners are reminded that plans are to be endorsed and stamped by Stockland prior to commencement and to ensure eligibility for the return of design and landscaping bonds on completion.

altrove

—  
***The Park Front***  
—



**Stockland**  
*it's your place*

***stockland.com.au/altrove***

**Disclaimer of Liability:** It should be noted that meeting the controls described in this Design Essentials document and securing endorsement from Stockland does not constitute an approval from your relevant Council or certification from an Accredited Certification Authority. In the event that Stockland allows a variation from these Design Essentials, the variation will neither set a precedent nor imply the approval will be repeated by Stockland or supported by an Accredited Certification Authority or relevant Council. All information is subject to change without notice.